



BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from Δ College to Δ Valley.

NARRATIVE

In 1978 I made two surveys in section 4, T 2 S, R 38 E, as hereon shown, Map of Survey numbers 73-78 and 148-78. These 1978 surveys required the retracement of a portion of the Township line as shown. I found the NW corner of section 5 and placed the NE corner of section 4. I then proportioned the corners between. In 1983 William L Hanley retraced the same portion of the Township line, Map of Survey 42-83. Mr Hanley found the N 1/4 corner of section 5 as shown. This effects my proportioned position of the NW corner and the N 1/4 corner of section 4. I used these corners to subdivide section 4 in 1978. In this correction survey I am subdividing section 4 on the basis of Hanley's retracement of the Township line. The resulting positions are as shown. Mr Hanley reset the NW corner of section 4 in 1983, see Map of Survey 42-83. He also set the W 1/4 corner of section 4. I proportioned the N 1/4 corner of section 4 and subdivided as shown. I pulled the seven monuments (5/8" X 30" rebar), and then reset them to the positions determined by this correction survey. I note the moves at each corner.

REGISTERED PROFESSIONAL LAND SURVEYOR
Duane J. Griffith
 OREGON JULY 14, 1984
 DUANE J. GRIFFITH
 644

REFERENCE MATERIAL

- Map of Survey no. 73-78
- Map of Survey no. 148-78
- Map of Survey no. 42-83

LEGEND

- Brass cap monument set by me in 1978.
- ⊙ Monument set by Hanley in 1983, see Map of Survey no. 42-83.
- Monument set by me in 1978, and reset this survey.
- () 5/8" X 30" rebar with plastic cap marked "BGA SURVEY MARK"
- () Bearing and distance by me in 1978, if other than found in this survey.
- [] GLO Record bearing and distance

UNION COUNTY SURVEYOR

Date Received 1-19-90

Date Filed 1-23-90

By R. ROBINSON, DEPUTY

File No. 1-90

AMENDING SURVEY

BAGETT - GRIFFITH & ASSOCIATES
 LaGrande, Oregon

MAP OF SURVEY
 T 2 S, R 38 E, SECTION 4
 Correction Survey for
 Map of Survey No's 73-78 & 148-78
 UNION COUNTY, OREGON

SURVEYED FOR	BAGETT - GRIFFITH & ASSOCIATES	
SURVEYED BY	d.i.g.	Jan, 1990
Scale: 1" = 500'	Drawn by: d.i.g.	Jan, 1990

Survey Number 1-90