



BASIS OF BEARING

Oregon Department of Transportation record bearing between centerline stations, 967 + 89.7 PT and 977 + 26.6 PS, bearing being S 63°45'30\"/>

NARRATIVE

This survey was made at the request of the Boise Cascade Corporation. The purpose of this survey was to remonument the East quarter corner of Section 18 in Township 1 North, Range 39 East of the Willamette Meridian.

A search for said corner turned up no evidence so I searched for the Northeast corner of the said Section 18. I found three original bearing trees in this location and reset this corner in the original position. I then located the Southeast corner of said Section 18, which had previously been remonumented. I commenced my survey at this point and ran Northerly to the Northeast corner of said Section 18. I used the data shown on Oregon State Highway Map, Drawing Number 5B-35-8, which has been duplicated in part on this plat. I used the ties this map shows from highway centerline station 967 + 89.7 PT to each of the original corners on the East line of said Section 18. The angle shown to the East quarter corner shows the reference line being on the spiral. I assumed this was a drafting error and used the tangent bearing between stations 967 + 89.7 PT and 977 + 26.6 PS which is the reference line for the other two lines shown. Using this data I mathematically computed relative positions of the involved corners. From the Southeast corner to the Northeast corner the computed distance was 5105.16 feet. My survey shows this distance to be 5118.52 feet. I proportioned the distances in the appropriated manner and set the quarter corner at this position.

I find no other problems with this survey.

LEGEND

- Found 2 1/2" brass cap of record
- ⊙ Found original evidence, set 2 1/2" x 30" aluminum cap
- ⊙ Set 2 1/2" x 30" aluminum cap at proportionate position based on Oregon State Highway Map, Drawing Number 5B-35-8
- Centerline station State Highway 204
- Centerline State Highway 204
- () Record information obtained from Oregon State Highway Map Number 5B-35-8
- ⤵ Record angles and distances stated on said state map

REFERENCE MATERIAL

Oregon State Highway Map, Drawing Number 5B-35-8.

General Land Office original survey notes.

UNION COUNTY SURVEYOR

Date Received 7-5-90

Date Filed 7-5-90

By Gregory I. Blackman

File No. 22-90

REGISTERED PROFESSIONAL LAND SURVEYOR

Gregory I. Blackman

OREGON
JULY 13, 1979
GREGORY I. BLACKMAN
991

BAGETT - GRIFFITH & ASSOCIATES
LaGrande, Oregon
Map of Survey

The East line of Section 18 in Township 1 North, Range 39 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR	BOISE CASCADE CORPORATION
SURVEYED BY	GTB
Scale: 1" = 400'	Drawn by: