

BASIS OF BEARING

Forward bearing as published by the U.S.C & G.S. from \(\triangle \) College to \(\triangle \) Valley, dated 1946.

LEGEND

- Found 5/8* tron pin with plastic cap marked
 AP&A set by Survey Number 15-83
- Found 2" Iron pipe with brass cap set by Survey Number 15-83
- Found 3/4" from pipe with cap marked + for North 1/4 corner Section 3 as per Union County monumentation records
- Found brass cap monument set by Highway
 Department for North 1/4 corner Section 3
 as per Union County monumentation records
- O Set 5/8" x 30" from pin with plastic cap marked BGA SURVEY MARKER

X X Existing fence line

() Record bearing and distance of Survey No. 15-83

____ Centerline

NARRAT I VE

This survey was done at the request of Stan Weishaar. I base my survey on Survey Number 15-83 by Gary Langlitz, OPLS 1099, which placed Sterling's 1st Addition and the Town of Island City at record distances called on the original plat. I agree with this location of Sterling's 1st Addition. I find that the State Highway diverges from the alignment of Sterling's 1st Addition along the North line of the addition. The highway was placed by Survey Number 8-85. This leaves a strip of the originally dedicated First Street between the North line of Blocks 8 and 9 of Sterling's 1st Addition and the State Highway right of way as shown. The fence along the South line of the surveyed parcel encroaches as shown. The parcel to the South has title to 100 feet of property North and South. The fence along the North line of Second Street is relative to the placement of the addition by Survey Number 15-83 and this survey. The fence encloses approximately 106 feet on the West line of the parcel and approximately 114 feet on the East line of the parcel. I find no other unusual conditions on this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR

RICK G. ROBINSON
2219

UNION COUNTY SURVEYOR

1 7/29/9/

By 11/4 Vy 7.Black

File No. 049-199/ BAGETT - GRIFFITH & ASSOCIATES

LaGrande, Oregon

Map of Survey

Lots I, 2 and the North 20'

of Lot 3, Block 8,

Sterling's 1st Addition

Island City

UNION COUNTY, OREGON

UNION COUNTY, OREGON		
SURVEYED FOR	Stan Weishaar	
SURVEYED BY	R.G.R.	7-91
Scale: "= 6	60" Drawn by: R.G.R.	7-91