South, Ranges 40 and 41 East. The basis of bearing observed on Survey Number 22-86 has been used on these surveys, all by Duane I. Griffith, OPLS 644. PREVIOUS REMONUMENTATIONS The Northwest corner of Section 2 William L. Hanley, OPLS 1639 (Index No. 121-89R) The North quarter corner of Section 2 October. 1991, at the request of the USDA Forest Service. In accordance with the statutes of the State of Oregon and with the articles of my contract.

I base my survey on the found monuments listed in the History of Surveys. The corners searched for but not found were originally posts with no accessories with the exception of the West 1/4 corner of Section 12. At this particular corner, Mr. Barr calls for two fir bearing trees. At the proportioned position there are no trees within 400 feet. I reestablish the corner by proportion. I accept the existing fence corner at the Southwest corner of Section 2 as being the best available evidence of the original corner position. The fence is harmonious with the surrounding corners set by Mr. Thempson as shown. This does create a shortage along the South line of Section 2. This is a portion of the Barr GLO contract. It is also in the mountainous terrain. Mr. Barr also called a house 3 chains East and 1.5 chains South of the Section corner. I could find no trace of the original structure, however there is a domestic apple tree approximately 50 feet South and 75 feet East of the house call from the corner using the fence corner as the corner position. I then establish the South quarter corner of Section 2 by single proportion.

I located the controlling corners and set the proportioned corners utilizing radial ties from prominent points, or points on the valley floor back to the face of the mountain, all within closed loops. The posting, with the exception of the West and South lines of the Southeast quarter of Section 12 and the Center-South 1/16 corner of Section 2 as shown.

I find no other unusual conditions on this survey. William L. Hanley, OPLS 1639 (Index No. 38-90R) The Northeast corner of Section 12 William L. Hanley, OPLS 1639 (Index No. 102-87R) The East quarter corner of Section 12 William L. Hanley, OPLS 1639 (Index No. 99-87R) The Southwest corner of Section II Gregory T. Blackman, OPLS 99! (Index No. 013-1991R) The Southeast corner of Section 11 Duane 1. Griffith, OPLS 644 (Index No. 259-86R) The Southeast corner of Section 12 Duane 1. Griffith, OPLS 644 (Index No. 461-84R) UNION COUNTY SURVEYOR Duane I. Griffith, OPLS 644
Bagett, Griffith and Associates
2006 Adams Avenue Date Received 11-7-91 LaGrande, Oregon October 29, 1991 Date Filed 11-8-9/ By R. ROBINSON DEPUTY File No. 057-1991

(S 89°26' E) Township 2 South 34 (\$ 89°20'36" E H) \$ 89° | 6'59" E 2766.03 Township 3 South (2765.09 H) (40 ch) Ea. SFNF 0 4 | 4 Range Range [80,43 chains] 5353,17 (39.90 ch.) (39.90 ch.) (\$ 89°29' W) 2541.22 SENE (\$ 89°29' W) 2541.22 S 86°48'20°E N 89°52'06" W N 89°58'35" W S 89°17'15" W 5082.44 2567.42 Accepted existing /10 10 (40.11 ch) (\$ 89°43' WJ (79.80 ch.) (\$ 89°30' E) (40.10 ch) Fence Corner as best available evidence of the original corner noificoq [60 ch. 5294. [2652,89 - N 88°55'50" W 5! 63. 27 Fence corner 40 ft. South & 12 ft. East of time collect 8 14 [80 chains] (2556.51 0) (2630.02 G) 5269.16 [40 Ch.] [40 ch.] SFNF 2558.73 2630, 24 N 88°46 59" S 89°47'28" W N 89°19'36" W [\$ 89°30' W] 14 13 (N 88°49'51" W G) [\$ 89°30" W] (N 89°19'44" W G) NATIONAL FOREST LANDS

TOWNSHIP 3 SOUTH, RANGE 40 EAST OF THE WILLAMETTE MERIDIAN

Section 1- The entire Section

Section 2- The East half

Section 12- The North Half and the Southeast quarter

For monumentation information, see monumentation sheets filed separately,

The information within these boxes is for U.S. Forest Service record keeping purposes only,

Examined and accepted for the U.S. Forest Service

I certify that this survey was performed at the request of the Wallowa Whitman National Forest. NATIONAL FOREST SUPERVISOR

PROJECT NAME Warm Creek Cadastral Survey (Phase II) CONTRACT NUMBER 00-04M3-1-0451

Number 1

Wild TC1600 Total Station FIELD BOOKS Traverse Book Numbers 1, 2 and 3 Remonumentation Book

Mac lie (infra-red) Geodineter Model 76 (Laser)

EQUIPMENT USED

Zeiss Th-2 Theodolite

Magnetic Declination 17° East

BASIS OF BEARING

The East line of the Southeast quarter of Section 12, Township 3 South, Range 40 East of the Willamette Meridian, as being North 2°35'57" West. (Same Basis of Bearing as Union County Survey Numbers 22-86, 29-86 and 33-88)

SOLAR OBSERVATION INFORMATION FROM SURVEY NUMBER 22-86 (Hour Angle Method)

Date June 17, 1986 Latitude 45°10'07" Longitude 117°45'06" Time 14:00:08 (GCT)

Found brass or aluminum monument as per Union County monumentation records. (See History of Surveys for Individual index numbers)

Set 2 1/2"x30" aluminum monument at position determined from original GLO survey evidence

Set 2 1/2"x30" aluminum monument at position determined by survey.

Record bearing and distance of GLO survey by W.B. Barr

Record bearing and distance of GLO survey by David T. Thompson

Record bearing and distance of GLO survey by Alonzo Gesner Record bearing and distance of survey number 16-73

Record bearing and distance of survey number 24-90

Posted National Forest Boundary

Privately owned land

National Forest Land

REGISTERED

PROFESSIONAL

KAND SURVEYOR

OREGON

DUANE 1. ORIFFITH

Corner searched for but not found

SURVEYOR'S CERTIFICATE

I. Duane I. Griffith. Registered Land Surveyor in the State of Oregon. hereby certify that this plat and the notes hereon, or attached, are a frue and correct representation of the survey I made in July. August and October, 1991, at the request of the USDA Forest Service, in accordance with the statutes of the State of Oregon and with the articles of my

ds shown.
I find no other unusual conditions on this survey.

BAGETT - GRIFFITH & ASSOCIATES LaGrande, Oregon Map of Survey

HISTORY OF SURVEYS

The Northwest corner of Section 2 was originally

established by Timothy W. Davenport under GLO

The South line of Sections II and 12, the West

were established by David T. Thompson under GLO contract number 103, dated September 3, 1863.

line of Sections 2 and 11 and the subdivision

of Township 3 South, Range 40 East, except Sections 1, 2, 11, 12, 24, 25, 26, 35 and 36

The North and East lines and subdivision of

The East line of Section 12 was retraced by

Alonzo Gesner under GLO contract number 683.

The South line of Section 12 was retraced by

Duane 1. Griffith, OPLS 644, on Union County

The East line of Sections I and 12 and the

by William L. Hanley, OPLS 1639, on Union

North line of Sections I and 2 were retraced

Survey Numbers 22-86, 29-86 and 33-88 Located

the National Forest Boundary in Townships 3 and 4

Sections 1. 2. II and 12 were originally established by W.B. Barr under GLO contract

number 355, dated June 14, 1880.

dated June 7, 1898,

Survey Number 16-73.

County Survey Number 24-90.

contract number 102, dated July 20, 1863.

National Forest boundary within Sections 2 and 12, Township 3 South Range 40 East, Willamette Meridian UNION COUNTY, OREGON

SURVEYED FOR | Wallowa Whitman National Fores SURVEYED BY 788-199 Scale: | "=1000" | Drawn by: R.G.R. 9-1991

<u>ا</u> Ŋ \circ (D)