

BASIS OF BEARING

Solar observation taken at a point 330 feet South and 6 feet West of the Northwest corner of Section 31, Township I North, Range 41 East of the Willamette Meridian. (Hour Angle Method)

> Date; Latitude; Longitude; Time;

November 15, 1991 45°31'40" 117°44'42" 18:19:04 (GCT)

REFERENCE MATERIAL

Original GLO Notes Union County Monumentation Records Survey Number 53-75 Survey Number 4-88

NARRATIVE

This survey was done at the request of Billy Hindman and Boise Cascade Corporation. The purpose of this survey was to mark the dividing line between the two ownerships. At the owners request, this line was also blazed. I found existing monuments at the North and South ends of the line and found evidence of the original GLO corner at the corner common to Sections 25, 30, 31 and 36. The quarter corner common to Sections 31 and 36 could not be found and I set a new monument at a position determined by survey. I find no other unusual conditions on this survey.

UNION COUNTY SURVEYOR

Date Received 11+21-91

Date Filed 11-21-91

By R. ROBINSON, DEPVTY

File No. 059-1991

BAGETT-GRIFFITH & ASSOCIATES

LaGrande, Oregon

Map of Survey
The Range line along the West line of S31
A the S1/2 of S30, T1N, R41E and the
East line of S 36 A the S1/2 of S25,
T1N, R40E, Willamette Meridian

UNION COUNTY, OREGON		
SURVEYED FOR	Billy Hindman - Bois	e Cascade
SURVEYED BY	G. T. B.	11-91
Scale: "= 500	Drawn by: R.G.R.	11-91