



BASIS of BEARING

Forward bearing as published by the U.S.C. and G.S. from Δ COLLEGE to Δ VALLEY Dated 1946.

REFERENCE MATERIAL

Amended plat of O'Connor's Addition
 Survey Number 21-64
 Survey Number 17-74
 Survey Number 78-80
 Survey Number 18-89
 Deed Volume 117 Page 465
 Deed Volume 143 Page 388
 Deed Microfilm No. 114921

NARRATIVE

This survey was done at the request of Laurie Hargett to locate the parcel shown. The parcel is described as Lot 8 except the East 15 feet and the adjoining vacated alley. I locate the block by retracing survey numbers 17-74 and 78-80, which established the position of K Avenue. I locate the intersection of 11th and L by single proportion along 11th St. from the positions determined by the previously mentioned surveys. I then drive a line to a point 10.00 feet (as called in survey no. 18-89) from the references on the manhole rim in the centerline of 8th. The distance between these points match the record distance within 0.02 ft. I found the monuments along the centerline of Hill Ave. as shown. I then locate the alley in Block 2 by proportioning the East line of the block and then driving a line at the average bearing of K and L Avenue to the East line of Hill Ave. as located by the found monuments. The plat of O'Connor's Addition does not dimension Lot 8. I therefore treat this as a remnant and give full width to lots 1 through 7. I place the East line of the parcel parallel with the East line of the block and the East line across Hill Ave. perpendicular with the centerline of Hill Avenue. I find the concrete bannister encroaches by 1 ft. at the Northwest corner of the vacated street as shown. I find no other unusual conditions on this survey.

LEGEND

- Found 3/4" Iron pipe set by Survey No. 18-89 unless otherwise noted
- Found monument as described
- Set 5/8"x30" Iron pin with plastic cap marked BGA SURVEY MARKER
- ⊗ Set "PK" nail in joint of pedestal at end of concrete bannister
- () Record distance of the amended plat of O'Connor's Addition to LaGrande
- [] Record distance of Survey No. 18-89
- Centerline

REGISTERED
**PROFESSIONAL
 LAND SURVEYOR**
Rick G. Robinson
 OREGON
 JULY 17, 1989
RICK G. ROBINSON
 2219

5-11-92
 5/18/92
Hyun J. Lee
 017-1992

BAGETT-GRIFFITH & ASSOCIATES
 LaGrande, Oregon
 Map of Survey
 A portion of Lot 8, Block 2
 and the adjoining vacated
 Hill Avenue, O'Connor's Addition
 LaGrande
 UNION COUNTY, OREGON

SURVEYED FOR	Laurie Hargett
SURVEYED BY	R. G. R. 5-92
Scale: 1"=50'	Drawn by: R. G. R. 5-92

Survey No. 017-1992