



REFERENCE MATERIAL

General Land Office field notes of GLO contract number 120 and 452.

Monumentation records filed in the office of the Union County Surveyor.

NARRATIVE

Survey was made at the request of Ted Atkinson to locate the East one sixteenth corner on the south line of section 32. The Township line was originally run by William H. O'Dell in 1867. O'Dell also subdivided the township to the north. In 1882 Herman D. Gradon retraced the township line in preparation to subdividing the township to the south. Gradon found considerable error in the O'Dell survey. Gradon retraced O'Dell's line, angling at the O'Dell corners and set section and 1/4 section corners pertaining to the south. I found the O'Dell and Gradon corners as shown. I placed the east one sixteenth corner at the mid point between the O'Dell south one quarter corner and the SE corner of section 32. I tied the north one quarter corner of section 32 to show relativity. I find no unusual conditions in this survey.

LEGEND

- Found monument as per monumentation records.
- Found evidence of original GLO corner set 2-1/2" x 30" aluminum pipe with cap.
- Set 2-1/2" x 30" aluminum pipe with cap by survey.
- Record bearing and distance, O'Dell survey.
- Record bearing and distance, Gradon survey.
- Existing fence line.

BASIS OF BEARING

Solar observations taken at a point 546 feet West of the SE corner of Section 32, Township 3 South, Range 37 East

NOTE

For corner setting data see monumentation records filed separately.

REGISTERED PROFESSIONAL LAND SURVEYOR

 OREGON JULY 10, 1984
 DUANE I. GRIFFITH
 644

11/23/92
 11/27/92
 Bryan T. Blackman
 045-1992

BAGETT-GRIFFITH & ASSOCIATES LaGrande, Oregon Map of Survey		
Portion of section 32 Township 3 South, Range 37 East Willamette Meridian UNION COUNTY, OREGON		
SURVEYED FOR	Ted Atkinson	
SURVEYED BY	dig	Nov. 1992
Scale: 1" = 500'	Drawn by: Lucy	Nov. 1992

Map of Survey 1992-045