

Survey No. 036-1991

Survey No. 124-78

East 1/4 Corner Section 8  
Found brass cap in water valve box



## BASIS of BEARING

Forward bearing as published by the U.S.C. and G.S. from  $\Delta$  COLLEGE to  $\Delta$  VALLEY  
Dated 1946.

### REFERENCE MATERIAL

Union County monumentation records  
Survey Number 124-78  
Survey Number 133-78  
Survey Number 036-1991

### DEED REFERENCES

Volume 141 Page 298  
Volume 142 Page 136  
Volume 150 Page 262  
Microfilm Number 112812

### LEGEND

- Found monument as described as per Union County monumentation records
- Found 5/8" iron pin with plastic cap marked BGA SURVEY MARKER set by survey as shown unless otherwise noted
- Found unrecorded 5/8" iron pin
- Set 5/8"x30" iron pin with plastic cap marked "BGA SURVEY MARKER"
- ⊗ Chiseled a 4 inch cross in a large piece of concrete with an area 15"x26" exposed
- x— Existing fence line
- - - Centerline
- ( ) Record distance of deed microfilm 112812

### NARRATIVE

This survey was done at the request of Gari Price to locate the parcel shown. I base my survey on the surveys listed in the reference material. I locate the North line along the South line of survey number 133-78, and the South line at record distance South of and parallel with that line. I locate the East line 30 feet West and parallel with the Section line, and the West line 40 feet East and parallel with the West line of 18th Street as monumented by survey numbers 124-78 and 036-1991. I find the existing fence lines to be harmonious as shown. I find no other unusual conditions on this survey.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Rick G. Robinson*

OREGON  
JULY 17, 1986  
RICK G. ROBINSON  
2219

Gekeler Lane

Southeast Corner Section 8  
Found brass cap in water valve box

11-18-92

11-18-92

D.I.G.R. (T) Deputy  
046-1992

BAGETT-GRIFFITH & ASSOCIATES LaGrande, Oregon		
Map of Survey		
Parcel in the Southeast quarter of Section 8, Township 3 South Range 38 East of the Willamette Meridian (A portion of unrecorded Russell Tracts) UNION COUNTY, OREGON		
SURVEYED FOR	Gari Price	
SURVEYED BY	R.G.R.	11-92
Scale: 1"=60'	Drawn by:	R.G.R. 11-92

Survey No. 046-1992