

## LEGEND

microfilm number 104194

 $\odot$ 

0

Found aluminum monument in water valve box as per Union County monumentation records unless otherwise noted

Set 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER

Centerline of roadway

Existing fence line

Record GLO bearing and distance

Record bearing and distance of survey number 23-80

Record bearing and distance of deed

## BASIS OF BEARING

Solar observation taken at the North 1/4 corner of Section 15, Township I North, Range 39 East of the Willamette Meridian.

### NARRATIVE

This survey was done at the request of Fred Rose. I find his and all of the adjoining property to be described as an aliquot portion of the section with the exception of the Miller parcel taken out of the NW corner of the North 1/2 of the SW 1/4 of the SW 1/4 of Section 4. In order to locate the parcel, a subdivision of Section 4 was necessary. I locate the section from the found corners as shown. I use the proportionate position for the East 1/4 corner of Section 4. The South 1/4 corner was established proportionately also. There is a North-South fence line running North, 14 feet East of the corner position. I do not accept this fence as perpetualing the location of the original 1/4 corner. The South half of the section was in one ownership until 1971. The fence is a new fence and I feel does not reflect the position of the original GLO 1/4 corner. I do however establish the position of the West 1/4 corner of the section at the intersection of the section line (established from the NE and NW corners of the section), and an existing fence line to the West of the corner. The land was patented in 1894, with the property division this fence represents being established in 1897. The original 1/4 corner was set in 1867. The corner did have two bearing trees at the time it was established. I feel that the position of the time of the corner was known at the time of the property division, and the fence was located from the original corner. In discussions with the current owners abutting this fence, I discovered that the fence was rebuilt in the late 1960s, replacing an old broken down fence, which I accept as the best available evidence of the original 1/4 corner position. This corner falls East of the county road as shown. The County Road Dept. drawing listed in the reference material also supports this position. I then subdivide the section as per the 1973 BLM Manual of Surveying instructions. The Miller parcel was deeded in 1980 as a metes and bounds description. I locate the Southwest corner of the Miller parcel at

#### REFERENCE MATERIAL

GLO Contract No. 120 Union County monumentation records Survey Number 26-70 Survey Number 23-80 Survey Number 030-1993 Union County Road Dept. location map of Valley View Road (Circa 1950)

#### DEED REFERENCES


Volume 31 Page 428
Volume 37 Page 32
Volume 40 Page 45
Volume 42 Page 175
Volume 48 Page 256
Volume 48 Page 256
Volume 156 Page 336
Microfilm Number 78803
Microfilm Number 78804
Microfilm Number 89794
Microfilm Number 104193
Microfilm Number 104193
Microfilm Number 10172
Microfilm Number 121073
Microfilm Number 138664

Microfilm Number 139107

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON
JULY 17, 1986
RICK G. ROBINSON
2219

Renewal Date: Dec. 31, 1994



# BAGETT-GRIFFITH & ASSOCIATES LaGrande, Oregon Map of Survey

Parcel in the North 1/2 of the Southwest 1/4 of the Southwest 1/4 of Section 4, Township | North, Range 39 East of the Willamette Meridian

	UNION COUNTY, OREGON	
SURVEYED FOR	Fred Rose	
SURVEYED BY	R.G.R.	3-94
Scale: As Noteo	Drawn by: R.G.R.	3-94