


## **CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

History of original corner establishment:

Cor. no. 2, (Goldie) on line 3-4 Lucky Break lode, of this survey. This point falls within a pine tree, 36 ins. diam., blazed and marked G-2-938 on N. and S. faces, from which:

A fir, 8 ins. diam., bears East, 22.5 ft. dist., mkd. G-2-938 BT. A fir, 8 ins. diam., bears N.28°E., 28 ft. dist., mkd. G-2-938 BT.



Description of corner evidence found:

Found 11/4" pipe 2.6' above ground. No mound of stone.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 3" diam. U.S.F.S aluminum capped pipe, 30" long, with magnet, 24"in ground and buried found pipe to the West.

for record on the	day of		Notice and the second s
State of	I hereby		instrument was filed in this office
Office of	1 / 0/	County of	
File No. 045-1994K	NARR. Draw	بعر	
By Algory Tablander			
	<u></u>		ROIL
Date Filed 11/22/94	ł		WAL 058
Date Received 8/18/94			NULY OF STOLL ROWALD 2058
	···		
UNION COUNTY SURVEYOR			PROFESSIONAL PROFE
			RESSIONEYOR TO
			OSTEREDONAL