

BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from \triangle COLLEGE to \triangle VALLEY Dated 1946.

REFERENCE MATERIAL

Plat of RYNEARSON'S ADDITION TO LAGRANDE

Survey Number 55 - 74 Survey Number 108 - 78

Deeds

MF 133792 MF 133793

LEGEND

Found Brass Plaque In water valve box set by Survey Number 106-78.

Set 5/8"x 30" rebar with plastic cap marked BGB SURVEY MARKER.

Found 5/8" rebar set by Survey Number 55-74

Centerline of Road

() Record distance on plat of RYNEARSON'S ADDITION

Existing fence line

Proposed easement line for ingress and egress

Record distance of McLain survey in 1922

NARRATIVE

This survey was ordered by Diana Loe. Mr. and Mrs. Loe owned lots 8, 9, 10 and 11. Lots 12, 13 and 14 are owned by Diana and Candie Dawn Loe. The Loe's are planning to place four manufactured homes on the lots shown above. The Loe's requested a lot line adjustment through the LaGrande Planning Commission and received approval to adjust seven lots to four larger lots. The letter of approval is dated July 21, 1994. The planners requested offstreet parking in the back of the properties. We are showning a 20 foot easement across the back of the lots for ingress and egress. The easements are granted by separate deeds.

by separate deeds.

My survey is based upon the found monuments originally set in 1922 by A. H. McLain, and remonumented by survey number 106-78. I find that survey number 55-74 incorrectly located the Northwest corner of this parcel 30 feet southerly of the found monument in Lake Street at Cedar. Mr. Voelz used a street width of 30 feet when the true width was 40 feet from the centerline of Lake. He further did not proportion the shortage of the land through the lats. I find him consistently more than 9 feet North and about a foot East of the true corners. Survey 106-78 located the exterior of Black 10, and was very harmonious with McLain. I base my entire survey on survey 106-78 and proportion the lots in the standard manner. I find that some of the fences do encroach onto the Loe property, however the Loe's indicated that they were going to remove the encroaching fences. The fences belonged to the previus owner, Mr. Eveson, who owned Lots 4 through 14, and the West 1/2 of Lot 3 of Black 10. I find no other problems with this survey.

UNION COUNTY SURVEYOR

Date Received 4/25/95 Date Filed 4/26/95

By R. ROBUSON, N. PUTY FILE NO. 011-1995 REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 13. 1973
GREGORY T.BLACKMAN
991

99 | Renewal Date: Dec. 31, 1995 LOT LINE ADJUSTMENT
Approved by LaGrande Planning Department

Dan Moore. Planning Director

BAGETT, GRIFFITH & BLACKMAN 2006 Adoms Avenue, LaGrande, Oregon

Map of Survey
LOT LINE ADJUSTMENT
LOTS 8 THROUGH 14 OF BLOCK 10
RYNEARSON'S ADDITION TO
LAGRANDE, OREGON

 SURVEYED FOR
 ELDEN R. & DIANA LOE

 SURVEYED BY
 GTB
 4-18-95

 Scale; 1* = 40 fT Drawn by: GTB
 4-20-95