



CURVE DATA

Ⓜ Total Curve West R/W R = 630.00' Δ = 30°19'55" L = 333.51' T = 170.76' L.C. = 329.63' S 15°08'29"E	Ⓜ Total Centerline Curve R = 600.00' Δ = 30°19'55" L = 317.63' T = 162.63' L.C. = 313.94' S 15°08'29"E
Ⓜ Curve W. of 030-1993 R = 630.00' Δ = 19°48'53" L = 206.88' T = 104.38' L.C. = 205.95' S 9°22'58"E	Ⓜ Curve E. of 030-1993 R = 630.00' Δ = 11°31'02" L = 126.63' T = 63.53' L.C. = 126.42' S 24°32'55"E

NARRATIVE

This survey was done at the request of Bob Wiles. The purpose of this survey is to monument the boundary line agreement recorded as Microfilm Numbers 160385 and 160386 in the deed records of Union County. I place the Easterly end of this line between the existing buildings as depicted on the map. The agreement line was placed by driving a line from the East end of the line placed as described, to a point 2 ft. South of the existing fence corner as directed by Mr. Wiles. I place the Westerly terminus of the line at a point 660.00 feet West of the intersection of the agreement line with the East line of Section 8. This is the record distance of the deed course in both Mr. Wiles and Mr. Schmittle's deeds. This line is approximately 2 feet South of an existing fence line. I base the location of the North and East lines of Section 8 on survey number 030-1995. I find no unusual conditions on this survey.

BASIS of BEARING

Solar observation taken at the North 1/4 corner of Section 15, Township 1 North, Range 39 East of the Willamette Meridian.

REFERENCE MATERIAL

- Original G.L.O. Survey Notes
 Union County Monumentation records
 Survey Number 26-70
 Survey Number 56-74
 Survey Number 030-1993
- DEED REFERENCES**
 Volume V Page 499
 Volume 38 Page 162
 Volume 156 Page 337
 Deed Microfilm Number 148041
 Deed Microfilm Number 160385
 Deed Microfilm Number 160386

LEGEND

- ⊙ Found monument as described, as per Union County monumentation records
- ⊙ Found 1 1/2"x30" aluminum monument set by survey number 030-1993
- ⊙ Found 5/8" iron pin with plastic cap set by survey number 030-1993
- ⊙ Set 5/8" iron pin with plastic cap marked BGB SURVEY MARKER
- () GLO record bearing and distance
- [] Record distance of Survey No. 26-70
- - - Centerline
- x - Existing fence line

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
Rick G. Robinson
 OREGON
 JULY 17, 1906
RICK G. ROBINSON
 2219
 Renewal Date: Dec. 31, 1998

**UNION COUNTY
 SURVEYOR**
 Date Received 8-11-95
 Date Filed 8/31/95
 By *J. Peterson*, Deputy
 File No. 027-1995

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey
 Monumentation of boundary line agreement in the Northeast 1/4 of Section 8, Township 1 North, Range 39 East of the Willamette Meridian
 UNION COUNTY, OREGON

SURVEYED FOR	Bob Wiles	
SURVEYED BY	R.G.R.	Aug. 1995
Scale: 1"=100'	Drawn by: R.G.R.	Aug. 1995

Survey Number 027-1995