

BASIS OF BEARINGS

S 89° 38' 32" E BETWEEN THE NW CORNER AND THE NE CORNER OF THE SE 1/4 OF SECTION 32, T1N, R38E, AS SHOWN ON UNION COUNTY SURVEY NO. 035-1995.

LEGEND

- ⊕ FOUND MONUMENT AS DESCRIBED
- SET 5/8" X 30" IRON ROD (CONCRETE REINFORCING ROD) WITH YELLOW PLASTIC CAP ATTACHED, MARKED "AP#A", UNLESS OTHERWISE NOTED
- △ RECORD POSITION AS SHOWN ON UNION COUNTY SURVEY NO. 38-80, POSITION NOT VISITED DURING THIS CORRECTION SURVEY
- | | RECORD DIMENSION AS SHOWN ON UNION COUNTY SURVEY NO. 38-80
- () RECORD DIMENSION AS SHOWN ON UNION COUNTY SURVEY NO. 43-83
- < > RECORD DIMENSION AS SHOWN ON UNION COUNTY SURVEY NO. 035-1995
- ① REFERENCE NUMBER-SEE SURVEY DATA REFERENCE TABLE

REFERENCE MATERIAL

UNION COUNTY SURVEY NUMBER 38-80
 UNION COUNTY SURVEY NUMBER 43-83
 UNION COUNTY SURVEY NUMBER 035-1995
 UNION COUNTY CORNER REMONUMENTATION RECORD NO. 423-83R
 UNION COUNTY CORNER REMONUMENTATION RECORD NO. 024-1995R
 UNION COUNTY CORNER REMONUMENTATION RECORD NO. 025-1995R
 UNION COUNTY CORNER REMONUMENTATION RECORD NO. 026-1995R

SURVEY NARRATIVE

THIS SURVEY WAS PERFORMED FOR THE PURPOSE OF CORRECTING THE LOCATION OF VARIOUS SURVEY MONUMENTS SET IN THE NE 1/4 OF SECTION 32, T1N, R38E, BY UNION COUNTY SURVEY NO. 43-83.

UNION COUNTY SURVEY NO. 035-1995 DESCRIBES THE NATURE OF THE SURVEY CORRECTIONS MADE TO UNION COUNTY SURVEY NO. 38-80. THESE CORRECTIONS RESULTED FROM THE TRANSPOSITION OF A SURVEY TRAVERSE DISTANCE DURING THE CONDUCT OF THE SURVEY IN 1980, WHICH CAUSED THE CALCULATED POSITION OF THE SE CORNER OF SECTION 32 TO BE IN ERROR AND WAS SUBSEQUENTLY REFLECTED IN THE POSITION OF PORTIONS OF THE EXTERIOR AND INTERIOR BOUNDARIES OF THE SECTION. THIS ERROR IN THE 1980 SURVEY ALSO CAUSED THE SUBDIVISIONAL CORNERS IN THE NE 1/4 OF THE SECTION TO BE INCORRECT.

THE FIELD WORK FOR THE CORRECTION OF THE POSITIONS OF THE CORNERS SHOWN ON THIS SURVEY WAS PERFORMED DURING AUGUST AND SEPTEMBER OF 1995, USING THE SAME TYPE OF FIELD EQUIPMENT AND METHODS AS DESCRIBED ON SURVEY 035-1995.


SURVEY DATA REFERENCE TABLE

- ① C-1/4-FD. 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 035-1995, MARKED "AP#A". ALSO FOUND THE CORNER ACCESSORIES AS DESCRIBED ON UNION COUNTY REMONUMENTATION RECORD NO. 025-1995R.
- ② C-E 1/16-FD. 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 035-1995. ALSO FOUND AN UNMARKED 5/8" IRON ROD BURIED 6", BEARING NORTH 5.17' AND EAST 10.67' (SEE SURVEY 035-1995). MONUMENT LOCATION IS 5' SOUTH OF AN EXISTING E-W FENCE AND 72' EAST OF A CORNER OF FENCES 5-E.
- ③ E 1/4 SEC. 32-FD. 5/8" IRON ROD WITH 2" ALUMINUM CAP, MARKED AS DESCRIBED ON UNION COUNTY REMONUMENTATION RECORD NO. 024-1995R. ALSO FOUND CORNER ACCESSORIES AS NOTED AND DESCRIBED ON SAID REMONUMENTATION RECORD NO. 024-1995R.
- ④ N 1/16 BET. SEC. 32 AND SEC. 33- MADE A DILIGENT SEARCH FOR THE MONUMENT SET BY SURVEY 43-83, MONUMENT WAS NOT FOUND. NO ADDITIONAL MONUMENTATION WAS ESTABLISHED.
- ⑤ NE 1/16- FD. A 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 43-83, BEARING NORTH 2.67' AND EAST 5.25'. REMOVED THE PLASTIC CAP AND BURIED THE IRON ROD 0.4'.
- ⑥ C-W-NE 1/64- FD. A 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 43-83, BEARING NORTH 2.24' AND EAST 2.63'. REMOVED THE PLASTIC CAP, UNABLE TO BURY THE FOUND IRON ROD.
- ⑦ C-N-S-NE 1/256- FD. A 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 43-83, BEARING NORTH 2.00' AND EAST 3.94'. REMOVED THE PLASTIC CAP AND BURIED THE IRON ROD 0.4'.
- ⑧ SE-NW-NE 1/256- FD. A 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 43-83, BEARING NORTH 1.84' AND EAST 2.95'. REMOVED THE PLASTIC CAP AND BURIED THE IRON ROD 0.4'.
- ⑨ NW-SW-NE 1/256- FD. A 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 43-83, BEARING NORTH 2.52' AND EAST 1.65'. REMOVED THE PLASTIC CAP AND BURIED THE IRON ROD 0.5'.
- ⑩ C-S-N 1/256- FD. A 5/8" IRON ROD WITH PLASTIC CAP PER SURVEY 43-83, BEARING EAST 2.25'. REMOVED THE PLASTIC CAP AND BURIED THE IRON ROD 0.5'.

CORRECTION OF UNION COUNTY SURVEY NO. 43-83

CORRECTION SURVEY

LOCATED IN THE NE 1/4 OF SEC. 32
 T.1N., R.38E., W.M., UNION COUNTY, OREGON

FOR: HOWARD PERRY	P.O. BOX 1107 LAGRANGE, OREGON 97030
SCALE: 1" = 500'	SHEET 1/1
DATE: AUG., 1995	 ENGINEERING • SURVEYING • MATERIALS TESTING LA GRANDE, OR. WALLA WALLA, WA. LEWISTON, ID.
JOB NO. 2697-61	

