



## BASIS OF BEARING

The north line of the Southwest 1/4 of Section 15, Township 4 South, Range 37 East of the Willamette Meridian being S 89°06'14" E as per Union County Map of Survey 3-89.



## LEGEND

- ⊙ Set 2 1/2" aluminum pipe monument with aluminum cap at position determined by survey. See monumentation sheet filed separately.
- Found 2 1/2" aluminum pipe monument with aluminum cap as per survey 3-89.
- Position of 2 1/2" iron pipe monument with 3" brass cap as per survey 3-89. Not visited this survey.
- ⊕ Position of 2 1/2" aluminum pipe monument with aluminum cap as per survey 3-89. Not visited this survey.
- ( ) Record information as per survey 3-89.

## NARRATIVE

This survey was performed at the request of Mr. Dick Snow. Mr. Snow requested that the Center West 1/16 corner of Section 15 be monumented. I find the Center 1/4 corner and the West 1/4 corner in place as per survey 3-89. The Center West 1/16 corner is then placed on line and midway between the above mentioned corners.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Gregory T. Blackman*  
OREGON  
JULY 13, 1973  
GREGORY T. BLACKMAN  
991  
Renewal Date: Dec. 31, 1997

## REFERENCE MATERIAL

Union County Surveyor Monumentation Records  
Survey 3-89

**UNION COUNTY  
SURVEYOR**  
Date Received 7-3-96  
Date Filed 7-3-96  
By J. Peterson, Deputy  
File No. 026-1996

**BAGETT, GRIFFITH & BLACKMAN**  
2006 Adams Avenue, LaGrande, Oregon  
Map of Survey  
North line of the SW 1/4  
of Section 15, Township  
4 South, Range 37 East of  
the Willamette Meridian.  
UNION COUNTY, OREGON

SURVEYED FOR	Dick Snow	
SURVEYED BY	GTB	6-96
Scale: 1" = 400'	Drawn by: JPP	7-96

026-1996