Centerline

Original Lot line prior to vacation

# BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from △ COLLEGE to △ VALLEY

Dated 1946.

SCALE: 1"=40"

### REFERENCE MATERIAL

Plat of Riverside Addition to LaGrande Plat of Cottonwood Estates Survey Number 80-77 Survey Number 106-78

#### DEED REFERENCES

Commissioners Journal Volume R Page 576 Deed Microfilm Number 90585 City of LaGrande Ordinance Number 2898

## **NARRATIVE**

This survey was done at the request of Albin Presley. The purpose of this survey is to adjust the existing lot lines within Block 69 of Riverside Addition to the configuration shown. The East line of the original block was located by driving a line between the found monuments of survey number 80-77. I place the South line of this ownership (along the centerline of vacated Polk Avenue) by extending the found monuments of survey number 80-77 Westerly to the East line of Columbia Street. Columbia Street was located by projecting the bearing between the found monuments of Cottonwood Estates North to Harney Avenue. I place Harney Avenue parallel with Polk Avenue, as indicated on map of survey number 80-77. Polk Avenue was vacated by Commissioners Journal R Page 576. The East 10 feet of the right of way of Columbia Street was vacated by deed microfilm number 90585. The alley within Block 69, the South 20 feet of right of way of Harney Avenue, and the West 10 feet of right of way of Union Street were vacated by LaGrande City Ordinance Number 2898. I monument the new configuration at the direction of Mr. Presley. The alphabetical designation on this map is shown to provide clarity in defining the newly configured parcels only. I find no unusual conditions on this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON
JULY 17, 1995
RICK 9. ROBINSON
2219

Renewal Date: Dec. 31, 1996

UNION COUNTY
SURVEYOR

Date Received 10-2-96

Date Filed

By Was 18(2)

By Aug 1 Black File No. 040-1996

# BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey

Lot Line Adjustment within Block 69, and the vacated alley, and vacated portion of the adjacent streets, Riverside Addition to LaGrande

SURVEYED FOR Albin Presley

SURVEYED BY R.G.R. 9-96

Scale;  $l:=40^{\circ}$  Drawn by; R.G.R. 9-96

rrvey Number 040-1996