



# BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from  $\Delta$  COLLEGE to  $\Delta$  VALLEY Dated 1946.

SCALE: 1"=100'

## LEGEND

- 5/8 x 30 Iron pin with plastic cap marked BGA SURVEY MARKER.
- Set copper clad with brass cap at precomputed position.
- ⊙ Set copper clad with brass cap in place of found pipe set by Survey No. 132.
- + Lead plug set by McClain Survey No. 1922.

## NARRATIVE

This survey was ordered by the CITY OF LAGRANDE in conjunction with a block grant to install sewer and water service to this area of the city. We started the survey prior to all of the construction by finding the remaining monuments set by A. H. McClain that were originally set in 1922, now filed as Survey Number 018-89. We also recovered the remaining monuments on centerline that were set by recorded surveys on file with the County Surveyor. We referenced the monuments and tied them into a closed loop traverse so that we could replace the monuments after construction. We replaced the monuments in the original positions, and then computed positions for the remaining intersections that had no original monuments, using single proportionate measurement between known monuments. I find no unusual conditions with this survey.

## REFERENCE MATERIAL

- |                  |                         |                          |
|------------------|-------------------------|--------------------------|
| Survey No. 67-70 | County Survey No. 28-78 | County Survey No. 27-75  |
| Survey No. 88-71 | County Survey No. 64-73 | County Survey No. 30-71  |
|                  | County Survey No. 9-69  | County Survey No. 109-73 |
|                  | County Survey No. 72-80 | County Survey No. 33-71  |
|                  | County Survey No. 32-76 | County Survey No. 83-153 |
|                  | County Survey No. 88-71 | County Survey No. 34-72  |
|                  |                         | County Survey No. 71-81  |
- McClain Survey No. 132  
 "Park Addition"  
 "Sugar Addition"

**UNION COUNTY SURVEYOR**  
 Date Received 8-13-97  
 Date Filed 8-13-97  
 By R. Robinson, Deputy  
 File No. 021-1997

REGISTERED PROFESSIONAL LAND SURVEYOR  
 GREGORY T. BLACKMAN  
 JULY 13, 1973  
 991  
 Renewal Date: Dec. 31, 1997

**BAGETT, GRIFFITH & BLACKMAN**  
 2006 Adams Avenue, LaGrande, Oregon  
 Map of Survey  
 SITUATED IN THE NW 1/4 OF THE NE 1/4 AND IN THE SW 1/4 OF THE NE 1/4 OF SECTION 5, TOWNSHIP 3 SOUTH, RANGE 38 EAST OF THE WILLAMETTE MERIDIAN, ALSO BEING A PORTION OF PARK AND SUGAR ADDITIONS

SURVEYED FOR	CITY OF LAGRANDE	
SURVEYED BY	GTB	7-1-1997
Scale: 1" = 100 Ft.	Drawn by: GTB	7-1-1997

SURVEY NO. 021-1997