



BASIS OF BEARING

The East line of Section 5, Township 1 North, Range 39 East of the Willamette Meridian being South 1°56'01" West, as per Union County survey number 023-1994.

SCALE: 1" = 500'

LEGEND

- Found monument as described as per Union County monumentation records
- ⊙ Set 2 1/2" aluminum monument from original GLO Survey evidence
- ⊙ Set 2 1/2" aluminum monument at position determined by survey
- Set 5/8"x30" iron pin with plastic cap marked "BGB SURVEY MARKER"
- [[]] Record information of GLO Contract No. 102
- [] Record information of GLO Contract No. 120
- () Record information of GLO Contract No. 579
- (()) Record information of survey number 1-81
- Existing fence line
- Posted line

NOTE:
For monumentation information, see monumentation record filed separately

NARRATIVE

This survey was done at the request of John Manwell of Boise Cascade Corporation. Mr. Manwell wanted to monument and mark the line between the Boise Cascade ownership and individual ownership in Section 5. The line is marked with steel fence posts. Mr. Manwell also wished to monument the 1/4 corner between Sections 7 and 8. The North line of Section 5 was previously located by survey number 1-81. The East line of the section was previously located by survey 017-1994. I found evidence of the original Southwest corner of the section. I found a well defined mound of stone, which fit the surrounding topography calls in the original GLO notes. Sections 4, 5, 6 and 7 were not surveyed at the time of the original subdivision of this township because of the mountainous terrain. The surveyor who did these sections apparently had difficulty with the terrain also. The distances and bearings between the found corners are very rough. A search was made for all of the missing GLO corners, but none were found. I place these corners by proportion and subdivide Section 5 in accordance with the BLM Manual of Surveying Instructions (1973). I find the existing fences to be away from the true property lines as shown. I also monumented the Westerly corners of the individual ownership within the Southeast 1/4 of the Southeast 1/4 of the section. These ownerships are all described as an aliquot portion of the section. This quadrant of the section is excessively short from the record dimension due to the shortage along the South line of the Southeast 1/4 of this section. The fence along the Westerly line of these ownerships is also well West of the true property line. I find no other unusual conditions in the course of this survey.

REFERENCE MATERIAL

Original GLO Contract Number 102 by Timothy W. Davenport, dated July 20, 1863
 Original GLO Contract Number 120 by Joseph G. Gray, dated May 27, 1867
 Original GLO Contract Number 579 by John W. Kimbrell, dated June 22, 1891
 Union County monumentation records
 Survey Number 26-70
 Survey Number 1-81
 Survey Number 017-1994

DEED REFERENCES
 Volume 153 Page 102
MICROFILM NUMBERS
 76195 154446
 129548 961861
 133623 961864
 134885 962609

REGISTERED PROFESSIONAL LAND SURVEYOR
 Rick G. Robinson
 OREGON JULY 17, 1996
 RICK G. ROBINSON 2219
 Renewal Date: Dec. 31, 1996

UNION COUNTY SURVEYOR
 Date Received 11-4-97
 Date Filed 11-4-97
 By [Signature]
 File No. 032-1997

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey
 Tract within Section 5 and the monumentation of the 1/4 corner common to Sections 7 and 8, Township 1 North, Range 39 East of the Willamette Meridian.
 UNION COUNTY, OREGON
 SURVEYED FOR Boise Cascade Corporation
 SURVEYED BY R.G.R. 10/97
 Scale: 1" = 500' Drawn by: R.G.R. 10/97

SURVEY NUMBER 032-1997