



BASIS OF BEARING
 Center of 3rd Street
 bears N. 52° 07' E;
 (Survey No. 43 - 1993)

NARRATIVE

This survey for Phillips Hodgson is for the purpose of marking on the ground with standard monumentation the corners of Lots 7-10, Block 13, North Powder Townsite. Preliminary traverse around Block 13 recovered street centerline intersections for all except Third and Center Street. That point lies on a line between "C" and "E" Street monuments; Centerline of Center Street bears S. 37° 47' 40" E, parallel to "C" Street, from 4th Street monument to intersect centerline of Third Street. Found monuments are described on the annexed drawing. The narrative on Survey No. 43-1993 contains information pertaining to this area in North Powder, too lengthy to repeat here.

REGISTERED PROFESSIONAL LAND SURVEYOR
James D. Hanley
OREGON
 SEPTEMBER 21, 1977
 JAMES D. HANLEY
 1206
 Renews June 30, 1999

LEGEND

- Set 5/8" X 30" rebar with plastic cap marked "HANLEY ENGR. PLS 1206".
- Found, monument as noted.

MAP OF SURVEY

T. 6 S., R. 39 E., W.M., SW1/4 NE1/4 SEC. 22
 IN LOTS 7-10, BLOCK 13
 NORTH POWDER, OREGON

SCALE: 1" = 50'
 Surveyed on September 18, 1997.

HANLEY ENGINEERING
 2043 MAIN STREET
 BAKER CITY, OREGON
 (541) 523-3803

UNION COUNTY SURVEYOR
 Date Received 11-4-97
 Date Filed 11-11-97
 By R. Robinson Deputy
 File No. 035-1997

Survey No. 035-1997