



SCALE: 1"=300'

BASIS OF BEARING

Solar observations taken at a point 1623.29 feet South and 22.32 West of the East 1/4 corner of Sections 13 and 18 Township 6 South Range 38 East of the Willamette Meridian

LEGEND

- ⊙ Set 2 1/2 x 30" aluminum monument.
- Existing ancient fenceline
- 1 1/2" Square wood stake (Hanley) placed by Hanley Co-ordinate.
- () GLO record bearing and distance

REFERENCE MATERIAL

GLO NOTES
William Hanley unrecorded map dated May, 1982.

NARRATIVE

This survey was completed by the Union County Surveyor for the purpose of documenting the work done by William Hanley for Doug Lewis. The maps that were viewed indicated many fence corner ties and the location of the two Quarter corners set by this survey. Mr. Hanley did not set any monuments, and according to Doug Lewis, Hanley was not instructed to set the monuments. The work was done on or about May 19, 1982, according to the correspondence reviewed by me. I located the 1/4 corner between Sections 13 and 18, Township 6 South, Range 38 and 39 East by intersecting the centerline of the Existing County road, and the ancient fences running East and West from the right of way fences. The 1/4 corner between Sections 25 and 30 of Township 6 South, Range 38 and 39 East were established in the same manner. The relativity of the lines of occupancy were very good. I find no other problems with this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR
Gregory T. Blackman
GREGORY T. BLACKMAN
991
Renewal Date: Dec. 31, 1999

UNION COUNTY SURVEYOR
Date Received 4-8-1998
Date Filed 4-20-1998
By R. ROBINSON DEPUTY
File No. 011-1998

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon
Map of Survey
Sited in Sections 13, 18, 19, 24, 25, & 30 all in Township 6 South, Ranges 38 and 39 East UNION COUNTY, OREGON
SURVEYED FOR UNION COUNTY SURVEYOR
SURVEYED BY CTB 3-24-98
Scale: 1" = 300 ft. Drawn by: CTB 3-24-1998

SURVEY NO. 011-1998