



LEGEND

- SET 5/8" IRON ROD WITH YELLOW PLASTIC CAP MARKED "APA."
- FOUND 5/8" IRON ROD, C.S. 60-70; POSITION REPORTED C.S. 15-81.
- ⊙ FOUND 5/8" IRON ROD, C.S. 15-81.
- ⊕ SECTION CORNER 4, 5, 8 AND 9; T. 3 S., R. 38 E., W.M.
- (XX) RECORD BEARING AND DISTANCE, C.S. 15-81.
- (XX) RECORD DISTANCE, PLAT OF HOME INVESTMENT ADDITION.

REFERENCES

C.S. 15 - 81
 PLAT OF HOME INVESTMENT ADDITION

NARRATIVE

THIS SURVEY WAS PERFORMED AT THE REQUEST OF RUSSELL PERRY TO MONUMENT THE BOUNDARIES OF THE THE PARCEL DESCRIBED AS FOLLOWS: THE NORTH 103.00 FEET OF LOT 3 AND THE WEST 9.00 FEET OF THE NORTH 103.00 FEET OF LOT 2, BLOCK 9, HOME INVESTMENT ADDITION; LA GRANDE, OREGON. ON THE GROUND WE RECOVERED MONUMENTS SET OR RECOVERED FROM C. S. 15-81 AND HELD THEIR POSITIONS AS REPORTED USING CALCULATED COORDINATES DEVELOPED WITH TRUE BEARINGS. THE MONUMENTS SET DURING THIS SURVEY WERE PLACED AT THE POSITIONS CALCULATED BY THE INTERSECTION OF A LINE THAT IS 103.00 SOUTHERLY AND PARALLEL WITH THE TRUE NORTH LINE OF LOTS 2 AND 3, AND A LINE 194.50 FEET EASTERLY AND PARALLEL WITH THE TRUE WEST LINE OF LOT 3, AND THE INTERSECTION OF THESE TWO LINES WITH THE LINES OF LOTS 2 AND 3.

THE EQUIPMENT USED WAS A LEITZ T1610 WITH DISTANCE INSTRUMENT AND A SOKKIA SDR-33 DATA COLLECTOR.

REGISTERED PROFESSIONAL LAND SURVEYOR
H. McLeod
 OREGON
 JAN. 21, 1992
 HARMON E. McLEODON
 2537
 Renewals 12/31/98

UNION COUNTY SURVEYOR
 Date Received 6-15-98
 Date Filed 6-25-98
 by R. Lawson, Deputy
 File No. 019-1998

MAP OF SURVEY
A PORTION OF LOTS 2 AND 3, BLOCK 9, HOME INVESTMENT ADDITION, LA GRANDE, UNION COUNTY, OREGON
SW 1/4, SEC. 5, T. 3 S., R. 38 E. W.M.

RUSSELL PERRY
 2303 N. SPRUCE
 LA GRANDE, OR.

SCALE: 1" = 40'
 DATE: MAY 1998
 JOB NO. 2720-80

anderson perry associates, inc.
 ENGINEERING • SURVEYING • MATERIALS TESTING
 LA GRANDE, OR. WALLA WALLA, WA. BAKER CITY, OR.

SHEET **1/1**

Survey Number 019-1998