



REFERENCE MATERIAL

Original GLO Contract Number 102
 (Dated July 20, 1863)
 Original GLO Contract Number 103
 (Dated September 3, 1863)
 Union County monumentation records
 Survey Number 1-87
 Survey Number 025-1996
 Survey Number 049-1996
DEED REFERENCES
 Volume 127 Page 343
 Volume 143 Page 4
 Volume 143 Page 5
 Volume 143 Page 6
 Microfilm Number 119846
 Microfilm Number 149104
 Microfilm Number 152868

BASIS OF BEARING

The monumented East line of Section 12,
 Township 1 South, Range 39 East of the
 Willamette Meridian being North 0°02'30" East,
 as per survey number 025-1996

SCALE: 1" = 400'

LEGEND

- ⊙ Found 2 1/2" brass cap monument as per Union County monumentation records
- Found 2 1/2" aluminum monument as per Union County monumentation records
- Found 5/8" iron pin with aluminum cap set by survey number 1-87
- ⊙ Set 2 1/2" x 30" aluminum monument (See monumentation record filed separately)
- Set 5/8"x30" iron pin with plastic cap marked "BGB SURVEY MARKER"
- [] Record information of GLO Contract No. 102
- () Record information of GLO Contract No. 103
- x-x-x- Existing fence line

NOTE:

For monumentation information, see monumentation records filed separately.

NARRATIVE

This survey was done at the request of Steve Gurnsey, on behalf of Boise Cascade Corporation. It was necessary to locate the North 1/4 corner and the Southwest corner of this section to properly subdivide the necessary portion of the section for the Boise Cascade ownership. I accept the existing fence corners as the best available evidence of both of these corners. The North quarter corner position is very harmonious with the other monumented corners of this section. The position of the Southwest corner does create a skewed line as shown. I searched for additional corners to the West of this position, but none were found. The original surveyor set posts with mounds of earth or stone, and made no topographic calls on the run to the West, even though there was topography to report. With no evidence to dispute the position of the fence corner as the section corner, I accept the fence as the best available evidence of the original corner position. I set a reference pin at the Northeast corner of the Boise Cascade ownership, 50 feet West and on the allat line from its intersection with the centerline of Indian Creek, which is the true East boundary line. I find no other unusual problems on this survey.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Rick G. Robinson
 OREGON
 JULY 17, 1988
 RICK G. ROBINSON
 2218
 Renewal Date: Dec. 31, 2000

UNION COUNTY
 SURVEYOR

Date Received 7/14/98
 Date Filed 7/15/98
 By Myron T. Deane
 File No. 022-1998

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey

Tract within the South half of Section 12,
 Township 1 South, Range 39 East
 of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR	Boise Cascade Corporation	
SURVEYED BY	R.G.R.	7-98
Scale: 1" = 400'	Drawn by: R.G.R.	7-98

SURVEY NUMBER 022-1998