



NARRATIVE

This survey was done at the request of John Manwell of Boise Cascade Corporation. Mr. Manwell wanted to monument and mark the lines between the Boise Cascade ownership and individual ownership in Sections 17 and 18. The lines are marked with steel fence posts. Previous surveys have monumented many of the controlling corners of these sections as shown. A search was made for all missing GLO corners, but none were found. I place these corners by proportion and subdivide Section 17 and 18 in accordance with the BLM Manual of Surveying Instructions (1973). The subdivision of sections 18 and 17 are somewhat skewed due to the 1/4 between 17 and 18 lying North of the midpoint of this line. This corner was set by original GLO evidence by survey no. 022-1990. The terrain is steep and heavily vegetated which probably caused the error in distances. This is also the probable cause of the skew along the North line of Section 18. Areas due East and West of the controlling section corners were searched, but no evidence of the original corner or its accessories were found. This area has been heavily logged and there is evidence of a fire in this area. I therefore set this corner by proportion. I find no other unusual conditions on this survey.

LEGEND

- Found monument as described as per Union County monumentation records
- ⊙ Set 2 1/2" aluminum monument at position determined by survey
- « » Record information of GLO Contract No. 102
- [] Record information of GLO Contract No. 120
- || || Record information of survey number 111-1978
- | | Record information of survey number 022-1990
- Posted line

REFERENCE MATERIAL

Original GLO Contract Number 102 by Timothy W. Davenport, dated July 20th, 1863
 Original GLO Contract Number 120 by Joseph G. Gray, dated May 27th, 1867
 Union County monumentation records
 Survey Number 006-1976
 Survey Number 111-1978
 Survey Number 022-1990
 Survey Number 032-1997

DEED REFERENCES

Volume 99 page 256
 Volume 142 page 392
 Volume 98 page 49
 Volume 99 page 298
 Microfilm No. 51612
 Microfilm No. 51820
 Microfilm No. 58350
 Microfilm No. 119345
 Microfilm No. 135165
 Microfilm No. 142830

REGISTERED
**PROFESSIONAL
 LAND SURVEYOR**
Rick G. Robinson
 OREGON
 JULY 17, 1998
**RICK G. ROBINSON
 2219**
 Renewal Date: Dec. 31, 1998

**UNION COUNTY
 SURVEYOR**
 Date Received 8/10/98
 Date Filed 8/29/98
 By *D. J. Blackman*
 File No. 025-1998

BASIS OF BEARING

Solar observation taken at the North quarter corner of Section 15, Township 1 North, Range 40 East of the Willamette Meridian.

SCALE: 1" = 600'

BAGETT, GRIFFITH & BLACKMAN 2006, Adams Avenue, LaGrande, Oregon Map of Survey		
Subdivisions of Sections 17 and 18, Township 1 North, Range 39 East of the Willamette Meridian UNION COUNTY, OREGON		
SURVEYED FOR	Boise Cascade Corporation	
SURVEYED BY	R. G. R.	8/98
Scale: 1" = 600'	Drawn by: N. W. V.	8/98

SURVEY NO. 025-1998