



BASIS OF BEARING

The East line of the Southeast quarter of Section 30, Township 5 South, Range 41 East of the Willamette Meridian being South 0°24'42" West, as per Union County survey number 051-1994

SCALE: 1"=500'

REFERENCE MATERIAL

Union County Monumentation Records
 Survey Number 19-86
 Survey Number 051-1994
 Dependent resurvey by Philip G. Griffin, BLM
 recorded on microfiche in the Union County Surveyor's Office

DEED REFERENCES

Deed Volume 134 Page 207
 Microfilm Number 27894
 Microfilm Number 80188

NARRATIVE

This survey was done at the request of Eileen Mulvehill. The purpose of this survey was to locate and mark the exterior of the South half of the Southeast quarter of Section 30 and the North half of the Northeast quarter of Section 31. A portion of this tract was marked as a part of a Forest Service Cadastral survey filed as survey number 051-1994 in the office of the Union County Surveyor. I accepted the monuments set by that survey and those set by the BLM as marking the controlling corners for the subdivision of these Sections. I then set my corner monuments at the position determined by standard proportion as per the BLM Manual of Surveying Instructions (1973). I set steel fence posts approximately 250 feet apart along the exterior of this tract to mark the true line. I set no new posts on the portion marked by survey number 051-1994. I find no unusual conditions on this survey.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
Rich G. Robinson
 OREGON
 JULY 17, 1986
 RICK G. ROBINSON
 2219
 Renewal Date: Dec. 31, 2000

LEGEND

- Found 2 1/2" aluminum monument set by survey number 19-86
- ⊙ Found 3" BLM Brass cap monument set by dependent resurvey by Philip G. Griffin
- ⊕ Found 3" aluminum cap on aluminum pipe set by survey number 051-1994
- ⊙ Set 2 1/2"x30" aluminum monument
- () Record information of dependent resurvey by Philip G. Griffin, BLM
- [] Record information of survey number 051-1994
- x—x—x— Line marked with steel fence posts set in conjunction with this survey
- /—/—/— Line previously marked with steel fence posts by survey number 051-1994

NOTE

For monumentation information, see monumentation sheets filed separately

UNION COUNTY SURVEYOR

Date Received 9-16-98

Date Filed 9/26/98

By *August Blackman*

File No. 035-1998

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey

Location of the South half of the Southeast quarter of Section 30 and the North half of the Northeast quarter of Section 31, Township 5 South, Range 41 East of the Willamette Meridian
 UNION COUNTY, OREGON

SURVEYED FOR	Eileen Mulvehill	
SURVEYED BY	R.G.R.	9/98
Scale: 1" = 500'	Drawn by: R.G.R.	9/98

SURVEY NUMBER 035-1998