



BASIS OF BEARING

Solar observation taken at a point 1247.40 feet North and 2644.07 feet West of the Southwest corner of Section 4, Township 1 South, Range 40 East of the Willamette Meridian

SCALE: 1" = 500'

REFERENCE MATERIAL

Original GLO Contract Number 450 by Henry Meldrum, dated December 1st, 1882
 Union County monumentation records
 Survey Number 032-1980
 Survey Number 033-1998
 Survey Number 039-1998

LEGEND

- Found 2 1/2" Aluminum cap monument set by survey number 039-1998
- ⊕ Found 2 1/2" Aluminum monument as per Union County Monumentation Records (unless otherwise noted)
- ⊙ Set 2 1/2" x 30" aluminum monument at position determined by survey
- () Record information of GLO contract No. 450
- x — Barb wire fence
- ▨ Swamp area

NARRATIVE

This survey was done at the request of Steve Gurnsey, on behalf of Boise Cascade Corporation, to determine positions of the South 1/4 corner, East 1/4 corner and Center 1/4 corner, of Section 16, and the West 1/16 between Sections 16 and 21. The Southeast Corner of Section 16 was previously monumented from the GLO record topographic calls to the boundary of a well defined swamp. The swamp constitutes an accessory and reestablishment by this means was superior to proportionate measure. The resulting location is very harmonious with the adjacent corners as shown. No evidence was found of the other corners. I set these corners by standard proportion from the found monuments. The existing fence lines are away from the true section lines as shown. I find no other unusual conditions on this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR
 RICK G. ROBINSON
 2219
 JULY 17, 1988
 OREGON
 Renewal Date: Dec. 31, 2000

UNION COUNTY SURVEYOR
 Date Received 10/16/98
 Date Filed
 By [Signature]
 File No. 043-1998

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey
 Subdivision of Section 16, Township 1 South, Range 40 East of the Willamette Meridian
 UNION COUNTY, OREGON
 SURVEYED FOR Boise Cascade Corporation
 SURVEYED BY R. G. R. 10/98
 Scale: 1" = 500' Drawn by: N. W. V. 10/98

SURVEY NUMBER 043-1998