



### BASIS OF BEARING

Solar observation taken at the Northwest corner of Section 19, Township 4 South, Range 40 East of the Willamette Meridian.

**SCALE: 1"=30'**

### REFERENCE MATERIAL

Plat of the Original Town of Union  
 Union City Ordinance 96-149  
 Survey Number 83-71  
 Survey Number 45-84  
 Survey Number 023-1996

**DEED REFERENCES**  
 Microfilm Number 963086  
 Microfilm Number 98137  
 Microfilm Number 982722  
 Microfilm Number 993741

### LEGEND

- Found 5/8" iron pin with plastic cap marked "BGA SURVEY MARKER" set by survey number 45-84
- Found 5/8" iron pin with plastic cap marked "BGA SURVEY MARKER" set by survey number 023-1996
- ⊕ Chiseled a 2" cross in the concrete sidewalk for property corner
- Set 5/8"x30" iron pin with plastic cap marked "BGB SURVEY MARKER"
- ( ) Record bearing of survey number 023-1996
- Centerline
- Original Lot or Block line

### NARRATIVE

This survey was done at the request of Leonard Almquist on behalf of the City of Union. The purpose of this survey is to monument a lot line adjustment along the South line of this surveyed tract. I place the exterior of the block by retracing survey number 45-84 to the South, and survey number 023-1996 to the North. Both of these surveys relied on survey number 83-71, which monumented the intersections of Main Street. The street has since been reconstructed and the monuments destroyed. I find a few seconds in rotation from survey number 023-1996 as shown. I place the South line of the surveyed tract at the direction of Mr. Almquist. I have also prepared legal descriptions for the City of Union and the adjoining owner to the South to accommodate the adjustment of their common boundary. I find no unusual conditions on this survey.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Rick G. Robinson*  
 OREGON  
 JULY 17, 1986  
 RICK G. ROBINSON  
 2219  
 Renewal Date: Dec. 31, 2000

UNION COUNTY  
 SURVEYOR  
 Date Received 7/22/99  
 Date Filed 8/05/99  
 By *R.G.R.*  
 File No. 017-1999

**BAGETT, GRIFFITH & BLACKMAN**  
 2006 Adams Avenue, LaGrande, Oregon  
 Map of Survey  
 Lots 7 and 8, Lots 1 and 2 excepting the West 20 feet, and the North 10 feet of Lot 3 excepting the West 20 feet, and the accruing portion of the vacated alley within Block 20 of The Original Town of Union UNION COUNTY, OREGON

SURVEYED FOR	City of Union	
SURVEYED BY	R.G.R.	4/99
Scale: 1" = 30'	Drawn by: R.G.R.	4/99

SURVEY NUMBER 017-1999