



### BASIS OF BEARING

A solar observation taken at the corner common to Sections 5 and 8.

SCALE: 1" = 500'

### LEGEND

- Found 2 1/2" Brass Cap monument as per Survey No. 37-86
- ⊙ Found 2 1/2" Brass Cap monument see Union County Monumentation Records.
- ⊙ Set 2 1/2" x 30" Aluminum monument at position of best available evidence of the original GLO corner (see Narrative)
- ⊙ Set 2 1/2" x 30" Aluminum monument at position determined by survey
- Set 5/8" x 30" iron pin with 1 1/2" Aluminum Cap at position determined by survey
- ( ) Record measurement original GLO Contract Number 450
- (( )) Record measurement Old Book of Surveys Page 252
- [ ] Record measurement Old Book of Surveys Page 281
- { } Record measurement Union County Survey No. 37-86
- x — Fenceline

### NOTE:

For monumentation information see monumentation sheets filed separately

### REFERENCE MATERIAL

- Original GLO contract Number 450, dated June 11, 1882, by Deputy Surveyor Henry Meldrum.
- Union County Monumentation Records
- Old Book of Surveys, Pages 252 and 281
- Survey No. 37-86

### NARRATIVE

This survey was performed at the request of Steve Gurnsey on behalf of BOISE CASCADE CORPORATION. Mr. Gurnsey wished to monument the corners of BOISE CASCADE CORPORATION's ownership in Section 5, Township 2 South, Range 40 East of the Willamette Meridian. This area has been logged heavily and there is virtually no evidence remaining of original GLO corners. The North line of Section 5 was established by Survey No. 37-86. I find the bearings and distances between said survey and this survey to differ as shown. Ancient blaze lines and supporting topo calls were used to establish the section corner common to Sections 5, 6, 7, and 8. Using this position I subdivided the section using standard proportionate procedure outlined in the 1973 BLM Manual of Surveying Instructions. I found the proportionate positions to fit the topo calls very well. I find no other problems with this survey.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Rick G. Robinson*  
OREGON  
JULY 17, 1986  
RICK G. ROBINSON  
2219  
Renewal Date: Dec. 31, 2000

UNION COUNTY  
SURVEYOR  
Date Received 8/26/99  
Date Filed 10/9/99  
By *Henry T. Clark*  
File No. 031-1999

**BAGETT, GRIFFITH & BLACKMAN**  
2006 Adams Avenue, LaGrande, Oregon  
Map of Survey

Section 5 of Township 2 South, Range 40 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR	BOISE CASCADE CORPORATION	
SURVEYED BY	R. G. R.	8/1999
Scale: 1" = 500'	Drawn by: N. W. V.	8/1999

SURVEY NO. 031-1999