

# BASIS OF BEARING

West line of the Northwest 1/4 of Section 29,  
being S 0°16'55"W as per Survey No. 1-81

SCALE: 1"=300'

## REFERENCE MATERIAL

Original GLO Contract Number 382, dated March 23,  
1881, by Deputy Surveyor Rufus S. Moore.

Union County Monumentation Records

### UNION COUNTY SURVEYS

Survey No. 7-70  
Survey No. 62-72  
Survey No. 33-79  
Survey No. 23-80  
Survey No. 71-80  
Survey No. 1-81

## LEGEND

- ⊙ Found Brass Cap Monument as per Union County Monumentation Records
- Found 5/8" iron pin with plastic cap marked BGA SURVEY MARKER set by Survey No. 71-80
- Found disturbed 5/8" iron pin with plastic cap marked BGA SURVEY MARKER set by Survey No. 1-81 unless otherwise noted
- ⊙ Found Brass Cap set by Survey No. 1-81
- X- Existing fenceline
- ▬ Blazed Line
- ( ) Record of original GLO Survey
- (( )) Record of Survey No. 62-72

## NOTES

I used a Leica TCA-1100 Total Station and circular prism in the establishment of the new accessories. The Basis of Bearing is the same as that on this survey. The distance to the bearing tree is to a 50d spike driven on the right side of the tree at the root crown. I attached a brass washer marked OPLS 2219 to the BT blaze.

## NARRATIVE

This survey was performed at the request of John Manwell on behalf of Boise Cascade Corporation. Mr. Manwell wanted to determine if the monuments on the North side of Boise Cascade Corporation's property had been moved. He also wanted to blaze the North and East lines of the said property. I base the location of the North and East lines on Survey No. 1-81. I found blaze lines on the North and East boundary. These were run sometime after Survey No. 1-81. These blaze lines are accurate and harmonious with my retracement of Survey No. 1-81. The original monuments of Survey 1-81 on the North line had been moved as indicated. I reset new monuments and freshened the blazes along the North and East lines. The existing fencelines are away from the property lines as shown. I find no other problems with this survey.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Rick G. Robinson*  
OREGON  
JULY 17, 1986  
RICK G. ROBINSON  
2219

Renewal Date: Dec. 31, 2000

UNION COUNTY SURVEYOR	
Date Received	11/30/99
Date Filed	12/4/99
By	<i>Henry T. Black</i>
File No.	041-1999

<b>BAGETT, GRIFFITH &amp; BLACKMAN</b> 2006 Adams Avenue, LaGrande, Oregon Map of Survey	
A survey of a portion of the West 1/2 of the Northwest 1/4 of Section 29, Township 2 North, Range 39 East of the Willamette Meridian	
UNION COUNTY, OREGON	
SURVEYED FOR	BOISE CASCADE CORPORATION
SURVEYED BY	R.G.R. 11/1999
Scale: 1" = 300 ft.	Drawn by: N.W.V. 11/1999

SURVEY NO. 041-1999