



BASIS OF BEARING

Solar observation taken at a point 1087 feet North and 1256 feet West of the Southwest corner of Section 31, Township 4 South, Range 41 East of the Willamette Meridian.
(Same Basis of Bearing as survey numbers 22-86, 31-86 and 29-88)

SCALE: 1" = 1000'

REFERENCE MATERIAL

- GLO Contract Number 235 by John H. Stone, dated July 6, 1875
- GLO Contract Number 320 by Henry M. Thatcher, dated April 1, 1879
- Survey by J.W. Kimbrell, dated April 19, 1888, recorded in Old Survey Volume on Page 57
- Union County Monumentation Records
- Survey Number 16-75
- Survey Number 22-86
- Survey Number 31-86
- Survey Number 29-88

NARRATIVE

This survey was done at the request of Stan Wilde, on behalf of Boise Cascade Corporation. The purpose of this survey was to mark the property line within the Southwest quarter of Section 31 and the Northwest quarter of Section 6. This area has had previous surveys in these sections as shown. The main area of confusion in these sections is the placement of the West half of the sections. There was an apparent error in the original surveys in these sections. This was discussed at length on survey number 31-86, which placed the West 1/16th corner between Sections 31 and 6. The error was also documented by the J.W. Kimbrell survey on page 57 of the old book of surveys. The controlling corners of Section 31 were in place, with the Northwest corner and West 1/4 corner of the section being previously placed mathematically, but not monumented. Many corners within Section 6 were previously monumented, but never correlated to each other. I did need to place the East 1/4 corner of Section 6. The area of this corner has been logged many times. I found no evidence of the original corner stone. I did find the remains of an ancient fence line running East and West through the area. In studying this area, it appears the Northerly 1/2 mile of the Sections in Township 5 South are short of the original GLO Survey dimensions. The ancient fence also reflects this trend. I place the East quarter corner of Section 6 at the intersection of the line between the Northeast and Southeast corners of the Section and the ancient fence line. I then subdivide the sections according to the BLM Manual. The existing fence along the posted line varies as shown. It appears the fence builders were unaware of the drastic shift in bearing along this line. I find no other unusual conditions on this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Rick G. Robinson

OREGON
JULY 17, 1986
RICK G. ROBINSON
2219

Renewal Date: Dec. 31, 2000

LEGEND

- Found 2 1/2" aluminum monument as per Union County monumentation records, set by survey as described
- Found 3" brass cap set in concrete, set by survey number 16-75
- Set 2 1/2"x30" aluminum monument with aluminum cap (See monumentation record filed separately)
- ⊙ Set 5/8" iron pin with 2" aluminum cap (See monumentation record filed separately)
- () Record information of GLO Contract number 320
- [] Record information of GLO Contract number 235
- { } Record information of Kimbrell survey recorded in the old book of surveys on page 57
- (()) Record information of survey number 16-75
- Existing fence line
- ++++ Posted line (Set steel fence posts at approximately 250 ft. intervals)

UNION COUNTY
SURVEYOR

Date Received 10/10/2000

Date Filed 10/31/00

By [Signature]

File No. 031-2000

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon

Map of Survey
Posting of Boise Cascade Lands within the Southeast quarter of Section 31, Township 4 South, Range 41 East, and in the Northwest quarter of Section 6, Township 5 South, Range 41 East of the Willamette Meridian.
UNION COUNTY, OREGON

SURVEYED FOR	Boise Cascade Corporation	
SURVEYED BY	R.G.R.	10/2000
Scale: 1" = 1000'	Drawn by: R.G.R.	10/2000

SURVEY NUMBER 031-2000