



BASIS OF BEARING

Solar observation taken at a point 130 feet South and 430 feet West of the North quarter corner of Section 13, Township 1 North, Range 40 East of the Willamette Meridian

SCALE: 1"=200'

LEGEND

- Found 2 1/2" aluminum monument set by Survey No. 21-84
- Found 2 1/2" aluminum monument as per Union County Monumentation Records
- Set 5/8"x30" iron pin with plastic cap marked BGB SURVEY MARKER
- ⊙ Set 5/8"x30" iron pin with 2" aluminum cap, see Union County Monumentation Records
- x — Fence line
- ////// Posted line Set steel fence posts along line at 250± ft. intervals
- () Record measurement GLO Contract Number 120, dated May 27, 1867
- [] Record measurement of Survey No. 95-74

REFERENCE MATERIAL

Union County Monumentation Records
 G.L.O. Contract No. 120, dated May 27, 1867
 UNION COUNTY SURVEYS
 Survey No. 95-74
 Survey No. 21-84

NARRATIVE

This survey was performed at the request of Carl Witherspoon. Mr. Witherspoon wished monument the corners and mark the lines of the tract as shown. This section was originally monumented and subdivided by Survey No. 21-84. I found monuments set by that survey and subdivide the Northeast quarter of the section as per the BLM Manual of Surveying Instructions (1973). The fence along the North line of Section 13 is South of the true Section line as shown. I find no other problems with this survey.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
Rick G. Robinson
 OREGON
 JULY 17, 1996
 RICK G. ROBINSON
 2219
 Renewal Date: Dec. 31, 2000

UNION COUNTY
 SURVEYOR
 Date Received 11/22/00
 Date Filed 12/27/00
 By *John T. Blue*
 File No. 035-2000

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey
 Situated in the Northeast 1/4 of Section 13,
 Township 1 North, Range 40 East of the
 Willamette Meridian
 UNION COUNTY, OREGON
 SURVEYED FOR CARL WITHERSPOON
 SURVEYED BY R.G.R. 11/2000
 Scale: 1" = 200' Drawn by: N.W.V. 11/2000

SURVEY NO. 035-2000