

to the existing fence. We then went through the lot line adjustment

process with the City of La Grande. (See Approval on the face of this

map). I also discovered a 0.35 ft. shift in the found pins set by survey

of the block were re-tied, and proved the location of the exterior to be

developments within Lot 12 of this block used a 60 ft. right of way for

substantiate the 80 ft. width for the right of way. I find the fence line

3rd Street. I found an unrecorded 3/4" iron pipe which also reflects

correct, but the pins set by the 1982 survey are North of the true

corner position by the 0.35 ft. distance. It also appears that the

on the North line of the Westerly tract to be away from the true

that placement. The original plat and the previous surveys all

Michael a. Hyle

City of LaGrande Community Development Director/Planning Director

REGISTERED number 16-82. The controlling monuments used to establish the exterior **PROFESSIONAL** LAND SURVEYOR OREGON JULY 17, 1986 RICK G. ROBINSON 2219 property line as shown. I find no other unusual conditions on this survey. Renewal Date: Dec. 31, 2002 BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from \triangle COLLEGE to \triangle VALLEY Dated 1946.

SCALE: 1"=50'

REFERENCE MATERIAL

Plat of the Original Town of Le Grand 1922 remonumentation of La Grande (Survey Number 18-89) Survey Number 42-73 Survey Number 60-81 Survey Number 16-82

DEED REFERENCES

Volume 145 Page 761 Volume 92 Page 406 Volume 146 Page 041 Volume 114 Page 620 Volume 137 Page 671 Volume 147 Page 667 Volume 147 Page 668 Volume 147 Page 669 Volume 138 Page 516 Volume 143 Page 666 Volume 145 Page 745 Volume 152 Page 549 Microfilm Numbers: 25514 31353 962441 113502

961740 971335

132635

LEGEND

27180

Found brass plaque in water valve box as per survey number 42-73

Found brass plaque in water valve box as per survey number 60-81

Found brass screw in lead plug in curbs set by survey number 18-89

Position of concrete monument set by survey number 18-89 (Monument destroyed by street construction, used record position of survey number 60-81)

Found crosses on manhole rim set by survey number 18-89

Found 5/8" iron pin with plastic cap marked "BGA SURVEY MARKER" set by survey number 16-82, 0.35' North of true corner position (See Narrative)

Found unrecorded 3/4" iron pipe

Set 5/8"x30" iron pin with plastic cap marked "BGB SURVEY MARKER"

Subdivision line

Existing fence line

Centerline

Record distance of survey number 18-89

Record distance of the Plat of Le Grand

UNION COUNTY SURVEYOR 7/2/01 022-2001

♣ BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon

Map of Survey Lot Line Adjustment situated in Block 4-D of the Original Town of Le Grand LaGrande

UNION COUNTY, OREGON Hometown Realty

SURVEYED FOR 6/2001 SURVEYED BY R.G.R. 7/2001 Scale: 1" = 50' Drawn by: R.G.R.