This survey was performed at the request of Stan Wilde on behalf of Boise Cascade Corporation. Mr. Wilde wanted to monument corners and post the lines around Boise Cascade's adjoining owner Rose Anne Bertwell Summers property. The exterior of Section 7 was monumented by Survey Nos. 63–79 and 42–83. The southeast corner of Section 7 was along a skid trail and appeared to have been hit by a bulldozer. All bearing trees had been cut down by logging within the last 10 years. I straightened the monument to the position established by the bearing tree stumps set by Survey Nos. 63–79. This position fit the record call of that survey around the East line of Section 7. I found the rest of the monuments set by said Surveys and accept their location. I retraced the surveys with a Leica 530 GPS unit. I established a local grid based on the average combined scale factor of the exterior of Section 7. Record distance of both surveys were very harmonious. The South 1/4 of Section 7 was declared lost after an extensive search. Logging in the area has destroyed all original evidence. I established the aliquot corners by standard procedure outlined in the BLM Manual of Surveying Instructions 1973. In addition to the SW1/4 of the SE1/4 Deed Book 84 Page 159 also conveys a tract described as, "beginning at the Northwest corner of the Southeast fourth (4) of Section Seven (7) township two (2) South range thirty eight (38) E.W.M. Thence east six rods, thence southwesterly to the southwest corner of the southeast quarter of the southeast quarter of section seven (7) township two (2) South Range thirty—eight (38) E.W.M. Thence North to the place of beginning..." I ran 6 rods easterly along the North line of the SE1/4 of the SE1/4 to enablish the Northeast corner of Mrs. Summer's property. There are fence remains along the East and South lines of Mrs. Summer's property. I have made calls to blaze lines. The blazes appear to be no more than 30 years old. I find no other problems with this Survey.

BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from △ COLLEGE to △ VALLEY

Dated 1946.

SCALE: 1"=500'

LEGEND

- Found 2 1/2" Brass Cap on 2" galvanized pipe as per Union County Monumentation Records or as noted.
- Found 2 1/2" aluminum monument, unless otherwise noted, as per Survey No. 42-83
- O Set 5/8"x30" iron pin with plastic cap marked BGB SURVEY MARKER
- Set 5/8"x30" iron pin with 2" aluminum cap, see Union County Monumentation Records filed separately
- Set 2 1/2"x30" aluminum monument at position determined by survey, see Union County Monumentation Records filed separately
- x Set steel fence post on property line
-) Record measurement of original GLO contract No. 452 by Herman D. Gradon, dated March 31 1882
-] Record measurement of Survey No. 42-83
- { Record distance of Deed Volume 84 Page 159

REFERENCE MATERIAL

UNION COUNTY MONUMENTATION RECORDS

GLO contract No. 452, by Herman D. Gradon, dated March 31, 1882.

UNION COUNTY SURVEYS Survey No. 63-79 Survey No. 45-83

DEED REFERENCES

Deed Volume 84 Page 159

PROFESSIONAL
LAND SURVEYOR

Date Received 6/07/2001

OREGON
JULY 17, 1986

RICK G. ROBINSON
2219

UNION COUNTY
SURVEYOR

Date Filed 7/2/01

By Mean 1:Bleken

023-2001

Renewal Date: Dec. 31, 2002

BAGETT, GRIFFITH & BLACKMAN

2006 Adams Avenue, LaGrande, Oregon Map of Survey

Situated in the South half of the Southeast quarter of Section 7, Township 2 South, Range 38 East of the Willamette Meridian UNION COUNTY, OREGON

SURVEYED FORBOISE CASCADE CORPORATIONSURVEYED BYR.G.R.6/2001Scale: 1" = 500'Drawn by: N.W.V.6/2001

VEY NO. 023-2001