



BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from Δ COLLEGE to Δ VALLEY Dated 1946.

REFERENCE MATERIAL

Union County Monumentation Records
 GLO Contract Number 102
 GLO Contract Number 103
 Survey Number 1-74
 Survey Number 33-74
 Survey Number 23-90
 Survey Number 27-90
 Survey Number 007-1996
 Survey Number 034-1998

SCALE: 1" = 500'

LEGEND

- Found 1 1/2" concrete filled pipe with brass screw as per Union County monumentation records
- ◆ Found aluminum monument set by survey number 27-90
- ⊙ Found 2 1/2" brass cap on 5/8" copper clad iron pin set by survey number 034-1998
- ⊕ Found 2 1/2"x30" aluminum monument set by survey number 034-1998
- ⊗ Set 2 1/2" brass cap on 5/8" copper clad iron pin
- ⊘ Set 2 1/2" aluminum cap on 5/8"x30" iron pin
- [] Record information of GLO Contract number 102 by Timothy W. Davenport, dated July 20, 1863
- () Record information of GLO Contract Number 103 by David P. Thompson, dated September 3, 1863
- x- Existing fence line
- - - Easement line

NOTE

For monumentation information, see individual monumentation sheets filed separately

NARRATIVE

This survey was done at the request of Sherilyn Rayburn. The purpose of this survey is to monument the exterior boundary of her ownership in Section 36. I base the location of the exterior of Section 36 on survey number 034-1998. I then subdivide the section by standard proportion in accordance with the BLM Manual of Surveying Instructions. The proportionate position of the West 1/4 corner of Section 36 is within 2 ft. in northings of an existing fence line running East. The fences on the interior of the section are away from the true proportionate position as shown. I find no other unusual conditions on this survey.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
Rick G. Robinson
 OREGON
 JULY 17, 1986
 RICK G. ROBINSON
 2219
 Renewal Date: Dec. 31, 2002

UNION COUNTY
 SURVEYOR
 Date Received 9-17-2002
 Date Filed 9/18/02
 By *Sherilyn Rayburn*
 File No. 034-2002

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey
 Location of tract situated in
 Section 36,
 Township 3 South, Range 38 East
 of the Willamette Meridian
 UNION COUNTY, OREGON

SURVEYED FOR	Sherilyn Rayburn	
SURVEYED BY	R.G.R.	9/02
Scale: 1" = 500'	Drawn by: R.G.R.	9/02

SURVEY NUMBER 034-2002