

This survey was ordered by Eastern Oregon Land Development LLC in order to define the exterior of the parcel in preparation of a topographic map for construction of a new building. I found the reference monuments, set on Survey Number 059–1994, for the centerline of Wallowa Lake Highway 82 at Stations 64+50 and at 75+00, both of which were set at 43 feet from centerline. With the centerline established, I then established the South line of said Highway at 62.00 feet from said centerline as per strip drawing number 10B–18–32. I then establish the centerline of Mulholland Drive from said strip drawing by converting the metric positions to feet. I found that the monument set at station 65+50, (referred to on strip map as NH3) was tied and given a co-ordinate. The intersection of Mulholland Drive and 26th street as well as the Pl's also had co-ordinates. I base my positions on the converted co-ordinates as shown on the strip map. I also found two monuments set by Survey Number 018–1987, that controlled the South line of the parcel that was intended to be surveyed. I extend the bearing between the two monuments 103.50 feet and run to the North at a right angle to said South line, (as shown by Survey 018–1987) to the intersection of the South line of Highway 82. I find no unusual conditions with this survey.

BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from △ COLLEGE to △ VALLEY

Dated 1946.

SCALE: 1"=100'

LEGEND

- Found Monument as noted, and as per Union County Remonumentation Record
- Found 5/8" iron pin with plastic cap marked "BGA SURVEY MARKER" set by survey number 018—1987
- Found 5/8" iron pin with plastic cap marked "BGB SURVEY MARKER" set by survey number 031—1996
- Found 5/8" iron pin with aluminum cap marked O.H.S.D. set by Survey Number 059—1994
- Set 5/8"x30" iron pin with plastic cap marked "BGB SURVEY MARKER"
- Existing fence line
 - Centerline of Street
 - Record grid bearing or distance as per O.S.H.D. drawing 10B—18—32

REFERENCE MATERIAL

Survey No. 042-71 Survey No. 087-72 Survey No. 018-1987 Survey No. 14-1992 Survey No. 059-1994 Survey No. 031-1996 0.H.S.D. Strip Map Drawing 10B-18-32

DEED REFERENCES

Microfilm No. 20053691 Microfilm No. 20053692 Microfilm No. 2004593 Microfilm No. 20046898 Microfilm No. 139493 Microfilm No. 128730 Book 90 Pg. 15 Book 139 Pg. 439 & 551 Book 158 Pg. 601 Book 159 Pg. 662


UNION COUNTY
SURVEYOR

Date Received 12/19/05

Date Filed 12/19/05

By R. Longueson Dentry

File No. 031-2005



Renewal Date: Dec. 31, 2005

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey

Situate in the East Half of the Northwest Quarter, and in the East Half of the Southwest Quarter of Section 4

of the Southwest Quarter of Section 4
Township 3 South, Range 38 East W.M.

Union County, Oregon

SURVEYED FOREastern OregonLand Development LLC.SURVEYED BYGTB11/22/05Scale: 1"= 100'Drawn by:GTB12/05/05