



5/8" rebar set by Survey No. 67-91.

STA. 109+46.46 P.O.T. BACK  
 N73°29'13"E 103.82  
 N86°17'23"E 143.06  
 S89°55'32"E 12.74  
 S89°55'32"E 12.74

109+46.46 P.O.T. AHEAD  
 N0°04'28"E 185.00  
 S89°55'32"E 89.49  
 S89°55'32"E 30.00  
 S89°55'32"E 30.00  
 S0°04'28"W 268.81  
 S0°04'28"W 119.32 [120]

82  
 268.81  
 119.32 [120]

**BASIS OF BEARING**

Forward bearing as published by the U.S.C. and G.S. from Δ COLLEGE to Δ VALLEY Dated 1946.

**SCALE: 1"=50'**

**LEGEND**

- Found monument as per Union county remonumentation records.
- Found 5/8" pin set by Survey number 44-83, unless otherwise noted.
- ▲ Found 5/8" pin with yellow plastic cap marked "BGA SURVEY MARKER", set by ISLAND WEST II.
- Found 5/8" rebar with yellow plastic cap marked "BGB SURVEY MARKER", set by Minor Partition number 1996-02.
- Found 5/8" rebar with yellow plastic cap marked "BGB SURVEY MARKER", set by Minor Partition number 1994-12.
- ◆ Found 5/8" rebar, set by Survey number 36-71.
- ⊕ Set 5/8" x 30" iron rebar with yellow plastic cap marked "BGB SURVEY MARKER", in concrete sidewalk.
- Set 5/8" x 30" iron rebar with yellow plastic cap marked "BGB SURVEY MARKER".
- × Position only from Survey number 41-81, nothing set.
- ( ) Record information from Survey number 41-81.
- { } Record information from Minor Partition 1994-012.
- Centerline of road
- - - - - Easement line

**REFERENCE MATERIAL**

Survey No. 67-91 Survey No. 44-83  
 Survey No. 41-81 Survey No. 36-71  
 Minor Partition No. 1994-12  
 Minor Partition No. 1996-02  
 ISLAND WEST II ADDITION

**DEEDS**

Microfilm No. 124612 Microfilm No. 139645

**NARRATIVE**

This survey was done at the request of the Light House Church. The Church was constructing a parking lot and requested that some of the existing property corner monuments, mainly along the North lines of the property to be located or reset. Surveys 36-71, 9-90 along with Minor Partitions 1994-12 and 1996-02 and ISLAND WEST II ADDITION previously monumented most of the Churches property. Shown on the above map are the monuments I recovered along with monuments that I did not find and remonumented at record positions. I find no unusual conditions with this survey.

UNION COUNTY SURVEYOR  
 Date Received 4/28/06  
 Date Filed 4/28/06  
 By *[Signature]*  
 File No. 011-2006

REGISTERED PROFESSIONAL LAND SURVEYOR  
*[Signature]*  
 OREGON JULY 17, 1986  
 RICK G. ROBINSON  
 2219  
 Renewal Date: Dec. 31, 2006

**BAGETT, GRIFFITH & BLACKMAN**  
 2006 Adams Avenue, LaGrande, Oregon  
 Map of Survey  
 Lots 6, 7 and 8 of Block 29 of STERLING'S ADDITION to Island City along with a parcel located in the Northeast 1/4 of Section 3, Township 3 South Range, 38 East of the Willamette Meridian Union County, Oregon

SURVEYED FOR	Light House Pentecostal Church
SURVEYED BY	R.G.R.
Scale: 1"= 50'	Drawn by: R.G.R. 4/7/06