



# BASIS OF BEARING

Solar observation taken at the Northwest corner of Section 19, Township 4 South, Range 40 East of the Willamette Meridian.

SCALE: 1"=50'

## REFERENCE MATERIAL

Plat of Hannah's Addition to Union  
 Survey Number 19-77  
 Survey Number 40-77  
 Survey Number 50-78  
 Survey Number 52-78  
 Survey Number 142-78  
 Survey Number 053-1994

### DEED REFERENCES

Microfilm Document Number 107139  
 Microfilm Document Number 131551  
 Microfilm Document Number 20080791

## LEGEND

- ▲ Found 5/8" Iron pin set by Survey Number 52-78
- Found 5/8" Iron pin with plastic cap marked BGA SURVEY MARKER set by Survey Number 053-1994
- Set 5/8" x 30" Iron pin with yellow plastic cap marked BGB SURVEY MARKER
- Centerline
- - - Existing Fenceline
- ( ) Record distance of the Original plat of Hannah's Addition to Union.

## NARRATIVE

This survey was done at the request of Silena Brettelle, owner of the land within. Ms. Brettelle wanted the exteriors of her property monumented. I base this survey on Survey Number 053-1994. The position of the blocks shown are as per that survey. The monuments of the 1994 survey were recovered in position. I use a standard proportion to determine lot dimensions. The portion excepted from the Brettelle ownership is described as the West half of Lot 7. A shed on the West side of the property extends slightly into the 4th St. right of way as shown. I find no other unusual conditions with this survey.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

OREGON  
 JULY 17, 1986  
 RICK G. ROBINSON  
 2219

Renewal Date: Dec. 31, 2008

UNION COUNTY  
 SURVEYOR

Date Received 9/2/08

Date Filed 9/2/08

By [Signature]

File No. 025-2008

**BAGETT, GRIFFITH & BLACKMAN**  
 2006 Adams Avenue, LaGrande, Oregon

Map of Survey  
 A Tract situated in Lots 5, 6, and 8,  
 and a portion of Lot 7,  
 Block 14  
 Hannah's Addition to Union  
 UNION COUNTY, OREGON

SURVEYED FOR	Silena Brettelle	
SURVEYED BY	R. G. R.	8/08
Scale: 1" = 50'	Drawn by: J. S. H.	8/08

SURVEY NUMBER 025-2008