



### BASIS OF BEARING

Solar observation taken at the Southwest corner of Section 15, Township 3 South, Range 40 East of the Willamette Meridian.

SCALE: 1" = 200'

### REFERENCE MATERIAL

Union County Monumentation Records  
 Survey Number 26-85  
 Survey Number 29-85  
 Field Notes of GLO Contract Number 102,  
 executed by T. Davenport, dated July 20, 1863

DEED REFERENCES  
 Microfilm Document Number 20045925

### LEGEND

- ⊙ Found 2 1/2" Aluminum monument set by Survey Number 26-85
- ⊙ Found 2 1/2" Aluminum monument set by Survey Number 29-85
- Found 2 1/2" Brass cap as per Union County Monumentation Records
- ⊙ Set 5/8" x 30" Iron pin with Aluminum cap marked as per Union County Monumentation Records
- Set 5/8" x 30" Iron pin with yellow plastic cap marked BGB SURVEY MARKER
- ( ) Record Bearing and Distance of Survey Number 29-85
- [ ] Record Bearing and Distance of GLO Contract Number 102, dated July 20, 1863.
- /// Line posted with steel fence posts

### NARRATIVE

This survey was done at the request of Craig Cox and Gallatin NE Land and Timber. The purpose of this survey was to monument the exteriors of his property. I recover the monuments set by Survey 26-85 and those reset by Survey Number 29-85 as well as those set by Gary Langlitz along the South line of the section. I divide the Southeast quarter of the section as per BLM Manual of Instructions 1973. I find no unusual conditions with this survey.

UNION COUNTY SURVEYOR  
 Date Received 10/6/08  
 Date Filed 10/6/08  
 By R. Rossman Denny  
 File No. 034-2008

REGISTERED PROFESSIONAL LAND SURVEYOR  
 Gregory T. Blackman  
 OREGON JULY 13, 1973  
 GREGORY T. BLACKMAN 991  
 Renewal Date: Dec. 31, 2009

**BAGETT, GRIFFITH & BLACKMAN**  
 2006 Adams Avenue, LaGrande, Oregon  
 Map of Survey  
 A tract of land situate in the Southeast quarter of Section 36, Township 3 South, Range 40 East of the Willamette Meridian  
 UNION COUNTY, OREGON  
 SURVEYED FOR Craig Cox and Gallatin NE Land and Timber  
 SURVEYED BY G. T. B. 10/08  
 Scale: 1" = 200' Drawn by: J. S. H. 10/08