



REFERENCE MATERIAL

Union County Monumentation Records
 Plat of La Grande Business and Technology Park Subdivision
 Plat of La Grande Town Houses
 Plat of Terra Lea Addition
 Survey Number 124-78
 Survey Number 006-1994
 Survey Number 013-1995
 Minor Partition 1994-03
 Minor Partition 1995-15
 Minor Partition 1996-05
 Minor Partition 1997-12
 Minor Partition 20010015T
 Minor Partition 20040007T
 Minor Partition 20050011T

BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from Δ COLLEGE to Δ VALLEY Dated 1946.

SCALE: 1"=100'

LEGEND

- Found monument as per Union County Monumentation Records
- Found 5/8" iron pin set by Survey Number 23-75
- Found 5/8" iron pin set by Survey Number 124-78
- ◆ Found 5/8" iron pin set by Survey Number 006-1994
- ◇ Found 5/8" iron pin set by Minor Partition Number 1994-03
- Found 5/8" iron pin set by Minor Partition Number 1995-15
- ⋄ Found 5/8" iron pin set by Minor Partition Number 1996-05
- ▲ Found 5/8" iron pin set by Minor Partition 1997-12
- △ Found 5/8" iron pin set by Minor Partition 20040007T
- ⊗ Found 5/8" iron pin set by Minor Partion 20050011T
- ⊕ Found 5/8" iron pin set by Terra Lea Addition
- Found 5/8" iron pin set by La Grande Business and Technology Park Subdivision
- ⋄ Brass screw and washer set by La Grande Town Houses
- () Record measurement of Minor Partition No. 1995-15
- [] Record measurement of Minor Partition No. 1997-12
- { } Record measurement of Survey Number 013-1995
- (()) Record measurement of Minor Partition No. 1996-05
- [[]] Record measurement of Minor Partition 20040007T
- {} Record measurement of Terra Lea Addition
-] [Record measurement of La Grande Business and Technology Park
-) (Record measurement of Minor Partition 20010015T
- Set 2" brass disc in concrete
- ⊙ Set 2 1/2" copper clad monument in water valve box, marked as per Union County Monumentation Records
- ⊕ Set 2 1/2" aluminum pipe marked as per Union County Monumentation records, filed separately

NARRATIVE

This survey was performed at the request of Norm Paullus on behalf of the City of La Grande. The purpose of this survey was to place centerline monuments after the reconstruction of Gekeler Lane. Many of the monuments that monument the right of way of Gekeler Lane are disturbed as well. The centerline intersection of Gekeler between 16th and 20th were reconstructed from the surveys that have monumented the right of ways as shown on the map. The position of Prospect Drive (originally platted as Grande Ronde Dr.) was determined from the pins that monumented MP 20050011T and La Grande Business and Technology Park. The monuments along Gekeler in this area seem to have been removed as well. Centerline was set for a 60 ft. right of way as it intersects the section line. The map shows Gekeler Lane as it existed at the time of the La Grande Business and Technology Park platting. In cooperation with a city of La Grande backhoe operator, a diligent search was conducted for the quarter corner between Sections 9 and 16 revealing no remaining evidence of the original corner. A monument was placed at single proportionate position. I find no other unusual conditions with this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR

R. G. Robinson
 OREGON JULY 17, 1886
 RICK G. ROBINSON
 2219

Renewal Date: Dec. 31, 2010

UNION COUNTY SURVEYOR

Date Received 4/9/09
 Date Filed 4/9/09
 By *J. S. H.*
 File No. 005-2009

BAGETT, GRIFFITH & BLACKMAN

2006 Adams Avenue, LaGrande, Oregon
 Map of Survey

Remonumentation of intersection monuments along Gekeler Lane, City of La Grande
 Situated in Township 3 South, Range 38 East of the Willamette Meridian

UNION COUNTY, OREGON	
SURVEYED FOR	City of La Grande
SURVEYED BY	R. G. R.
Scale: 1"=100'	Drawn by: J. S. H. 3/09