



BASIS OF BEARING

The West line of Southwest quarter of Section 4, Township 4 South, Range 37 East of the Willamette meridian being S 1°45'21" E, as per Survey Number 019-2005

SCALE: 1" = 500'

REFERENCE MATERIAL

Field Notes of GLO contract #120, dated May 27, 1867, executed by William Odell
 Field Notes of GLO contract #452, dated June 16, 1882, executed by Herman D. Gradon
 Union County monumentation records
 Survey Number 045-1992
 Survey Number 022-1996
 Survey Number 032-2004
 Survey Number 019-2005

DEED REFERENCES
 Microfilm Document Number 20085035

LEGEND

- ⊙ Found monument as per Union County Monumentation Records
- ⊙ Found 2 1/2" Brass cap on 1 1/2" iron pipe, set by Survey Number 032-2004
- ⊙ Found 2 1/2" Brass cap on 1 1/2" iron pipe, set by Survey Number 019-2005
- Set 5/8" x 30" iron pin with 2 1/2" Aluminum cap, marked as per Union County Monumentation Records, filed separately
- ⊙ Set 2 1/2" Aluminum pipe with cap at proportionate position, marked as per Union County Monumentation Records, filed separately
- ⊙ Set 2 1/2" Aluminum pipe with cap at original GLO stone position, marked as per Union County Monumentation Records, filed separately
- () Record measurement as per Survey Number 019-2005
- [] Record measurement as per GLO contract Number 452, dated June 15, 1882
- Line posted with steel fenceposts
- Steel fenceposts set on line
- Creek

NARRATIVE

This survey was done at the request of Kirk Fenley, ranch manager for Jordan Creek Ranch. Mr. Fenley wanted the ownership within the Southeast quarter Section 4, Township 4 South, Range 37 East located and marked. Monuments of record were recovered as shown. The Northeast corner of Section 4 was a stone of correct size and markings, found in an old rock jack. 1 monument the position of the stone. No original evidence at the East and South quarter corners could be found. I place these by proportionate position. Subdivision of the section was done as per BLM Manual of Instructions 1973. Monumentation records are filed separately. I find no unusual conditions with this survey.

UNION COUNTY SURVEYOR	
Date Received	6/1/09
Date Filed	6/1/09
By	Rick G. Robinson
File No.	011-2009

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 17, 1986 RICK G. ROBINSON 2219

Renewal Date: Dec. 31, 2010

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey
--

Situated in the Section 4, Township 4 South, Range 37 East of the Willamette Meridian

UNION COUNTY, OREGON		
SURVEYED FOR	Kirk Fenley	
SURVEYED BY	R. G. R.	5/09
Scale: 1" = 500'	Drawn by: J. S. H.	5/09

SURVEY NUMBER 011-2009