



BASIS OF BEARING

The East line of the Southeast quarter of Section 18,
Township 1 South, Range 40 East of the Willamette Meridian
being North 0°01'17" East, as per Survey Number 045-1998

SCALE: 1" = 400'

LEGEND

- Found monument as per Union County monumentation record, as noted
- Set 2 1/2" x 30" aluminum pipe monument with aluminum cap marked as per Union County Monumentation record, filed separately
- [] Record measurement as per Survey Number 025-1996
- () Record measurement as per Survey Number 045-1998
- { } Record measurement as per field notes of GLO contract No. 450, dated June 11, 1882 by Henry Meldrum
- Steel fencepost set on line
- ////// Line marked with orange paint on trees

REFERENCE MATERIAL

- Union County Monumentation Records
 Survey Number 37-86
 Survey Number 025-1996
 Survey Number 034-1996
 Survey Number 043-1998
 Survey Number 045-1998
 Survey Number 042-2004

Field Notes from GLO contract no. 450, dated
June 11, 1882 completed by Henry Meldrum

NARRATIVE

This survey was done at the request of Dan Bennett, on behalf of Hancock Forest Management, timber manager for the lands within. Mr. Bennett wanted the line common to Sections 19 and 20 and a portion of the line between Section 17 and 18 marked. The line lying North of Indian Creek was marked with orange paint on trees falling close to line. South of the creek the line was marked with steel fence posts on line. A diligent search revealed no evidence of the original quarter corner between Sections 19 and 20. Although proportionate position does not appear to fit the topographic call to Indian Creek, as per original GLO field notes, I feel the Northwesterly skew of Indian Creek and the steepness of the terrain could have contributed to this discrepancy. I place the corner at proportionate position.

I find no other unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2013

UNION COUNTY
SURVEYOR

Date Received 7/27/12

Date Filed 7/27/12

By R. Robinson, Deputy

File No. 026-2012

| | |
|---|------------------------------|
| BAGETT, GRIFFITH & BLACKMAN | |
| 2006 Adams Avenue, LaGrande, Oregon | |
| Map of Survey | |
| East line of the Southeast quarter of Section 18 and the line common to Section 19 and 20, Township 1 South, Range 40 East of the Willamette Meridian | |
| UNION COUNTY, OREGON | |
| SURVEYED FOR | Hancock Forest Management |
| SURVEYED BY | J. S. H. |
| Scale: 1" = 400' | Drawn by: J. S. H. July 2012 |

SURVEY NUMBER 026-2012