



FOUND A SCRIBED "X" IN CONCRETE SET BY CS 17-79, ON JUNE 2, 2011. SURVEY MONUMENT WAS REMOVED BY SIDEWALK CONSTRUCTION, AND REPLACED WITH A 5/8 INCH IRON ROD 30 INCHES LONG WITH 1 1/2" DIA. ALUMINUM CAP STAMPED "APA WA41295 OR2849."

**SURVEY NARRATIVE**

THIS SURVEY WAS PERFORMED IN ACCORDANCE WITH ORS 209.150(1) WHICH REQUIRES ANY PERSON OR PUBLIC AGENCY REMOVING, DISTURBING OR DESTROYING A MONUMENT OF RECORD, TO REPLACE SAID MONUMENT. AS PART OF THE RECONSTRUCTION OF DEARBORN STREET, A MONUMENT AT THE SOUTHWEST QUADRANT OF THE INTERSECTION OF DEARBORN STREET, AND FOURTH STREET, SET BY CS 17-79, WAS LOCATED AND TIED PRIOR TO CONSTRUCTION. AFTER CONSTRUCTION WAS COMPLETED, THIS MONUMENT WAS REPLACED AS PER ORS.

NO BOUNDARY DETERMINATION WAS MADE WITH THIS SURVEY. SAID NEW MONUMENT WAS SET AT THE LOCATION WHERE IT WAS FOUND PRIOR TO CONSTRUCTION.

**BASIS OF BEARINGS**

N88°46'26"E BETWEEN THE FOUND MONUMENTS WAS DETERMINED BY ORGN GPS OBSERVATIONS-OREGON COORDINATE SYSTEM, NORTH ZONE NAD 83(CORS 96).

**LEGEND**

- INDICATES SET 5/8 INCH IRON ROD, 30 INCHES LONG WITH 1 1/2" DIA. ALUMINUM CAP STAMPED "APA WA41295 OR2849", DOWN 0.1 BELOW SURFACE.
- △ INDICATES FOUND MONUMENT AS DESCRIBED HEREON
- INDICATES ROAD RIGHT-OF-WAY
- - - INDICATES ROAD CENTERLINE
- ( ) MEASUREMENT PER RECORD

**REFERENCES**

- CS 17-79
- CS 50-78
- CS 52-78
- CS 15-79
- CS 33-77



DATED: 01-07-2013

<b>UNION COUNTY SURVEYOR</b>	
Date Received	1/14/13
Date Filed	1/14/13
By	Rick Robinson
File No.	002-2013

<b>MAP OF SURVEY</b> CORNER RESTORATION ON DEARBORN STREET, AND FOURTH STREET, IN THE CITY OF UNION, UNION COUNTY OREGON IN THE NW 1/4, SECTION 19, T.45., R.40E. W.M.,	
UNION COUNTY ROAD DEPT. SCALE: 1" = 50' DATE: JAN. 4, 2013 JOB NO. 863-122	10515 N. McALISTER RD ISLAND CITY, OR. 97130 <b>anderson perly</b> & associates, inc. ENGINEERING · SURVEYING · MATERIALS TESTING LA GRANDE, OR. WALLA WALLA, WA. SHEET <b>1/1</b>