



Found 2 1/2" iron pipe with 3" brass cap marked as per Umatilla County monumentation record H-164-R.

Found 2 1/2" iron pipe with 2" brass cap marked as per Umatilla County monumentation record 82-109-R

Corner searched for, not found. Set corner at proportionate position.

Found 5/8" iron rebar with 2 1/2" aluminum cap, set by Survey Number 036-2012

Found 2 1/2" aluminum pipe with 2 1/2" aluminum cap, set by Survey Number 036-2012

Found 2 1/2" aluminum pipe with 2 1/2" aluminum cap, set by Survey Number 036-2012

Found 2 1/2" iron pipe with 3" brass cap marked as per Union County monumentation record 223-84R.

BASIS OF BEARING

True Geodetic North at the corner common to Section 33 and 34, Township 1 South and Section 3 and 4, Township 2 South, Range 36 East of the Willamette Meridian, as determined by GPS observation (NAD-83 (1991) datum)

SCALE: 1" = 500'

LEGEND

- Found monument as noted, marked as per Umatilla/Union County Monumentation Records
- Set 2 1/2" x 30" Aluminum pipe with cap marked as per Umatilla County monumentation records, filed separately
- Set 5/8"x30" rebar with 2 1/2" aluminum cap, marked as per Umatilla County monumentation records, filed separately
- [] Record measurement as per GLO Field notes for Contract No. 452, executed by Herman Gradon
- Set steel fencepost on line
- //// Line marked with flagging and paint on adjacent trees

REFERENCE MATERIAL

Union County Monumentation Records
 Umatilla County Monumentation Records
 Union County Survey Number 036-2012
 GLO Field Notes for Contract No. 452, executed by Herman D. Gradon, dated June 16, 1882

NARRATIVE

This survey was performed at the request of Steve McClelland on behalf of Hancock Forest Management, land manager for the lands within. Mr. McClelland wanted the lines shown hereon marked with paint and flagging for logging purposes. A diligent search for the West quarter corner of Section 33 revealed no evidence of the original corner. I place the corner at proportionate position. I divide the section as per BLM Manual of Instructions 2009. The names shown hereon are internal divisions within the Hancock Forest Management group. I find no other unusual conditions with this survey.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON
 JUNE 2, 2010
 JEFFREY S. HSU
 83571
 Renewal Date: June 30, 2015

UNION COUNTY SURVEYOR

Date Received 5/6/13

Date Filed 5/6/13

By J. S. H.

File No. 020-2013

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey

Situated in Section 33, Township 1 South, Range 36 East of the Willamette Meridian

UMATILLA/UNION COUNTY

SURVEYED FOR Hancock Forest Management

SURVEYED BY J. S. H.

Scale: 1" = 500' Drawn by: J. S. H. May 2013