

## BASIS OF BEARING

Solar observation taken at the North quarter corner of Section 15, Township 1 North, Range 39 East of the Willamette Meridian.

**SCALE: 1" = 1000'**

## LEGEND

- Found monument as described, marked as per Union County Monumentation Records
- Set 2 1/2" aluminum pipe with 2 1/2" aluminum cap as proportionate position, marked as per Union County monumentation records, filed separately
- Set 5/8" x 30" Iron pin with 2 1/2" aluminum cap, marked as per Union County monumentation records, filed separately
- ◇ Set 5/8" x 30" iron pin with yellow plastic cap marked BGB SURVEY MARKER
- Set steel fence post on line
- [ ] Record measurement as per GLO survey by Rufus Moore, under Contract No. 382, dated March 12, 1888
- ( ) Record measurement as per Survey Number 65-81
- Line marked with flagging and paint on adjacent trees
- x — Existing fenceline

## REFERENCE MATERIAL

- Union County Monumentation Records
  - Survey Number 1-81
  - Survey Number 65-81
  - Survey Number 16-89
- Field Notes of GLO Contract No. 382, executed by Rufus Moore, dated March 12, 1888
- DEED REFERENCES**  
Book 147, Page 193

## NARRATIVE

This survey was done at the request of Steve McClelland, on behalf of Hancock Forest Management, land manager for the lands within. Mr. McClelland wanted the lines, as shown hereon, marked with flagging and paint on adjacent trees in preparation for a timber sale. I recover the monuments along the East line of Section 19 as shown hereon and find them harmonious with Survey Number 65-81, with the exception of the South-South 1/64th corner. I set a new monument at this corner and drive the old pin below the surface. I make a diligent search for the GLO corners within Section 19, and find no remaining evidence of them. I proportion the monuments in as per BLM Manual of Instruction 2009. Along the Southeast corner of Section 19, a fenceline falls approximately 40 feet West (at the South-South 64th corner), meandering South, where it falls approximately 2 feet West of the Southeast section corner. Steel fenceposts were set on line where they fall against the exterior of lands managed by Hancock and at road intersections. Names of owners shown hereon are internal designations within Hancock Forest Management. I find no other unusual conditions with this survey.

<b>UNION COUNTY SURVEYOR</b>	
Date Received	6/3/13
Date Filed	6/3/13
By	<i>MLG</i>
File No.	024-2013

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>Jeffrey S. Hsu</i>
OREGON JUNE 2, 2010 JEFFREY S. HSU 83571
Renewal Date: June 30, 2013

<b>BAGETT, GRIFFITH &amp; BLACKMAN</b> 2006 Adams Avenue, LaGrande, Oregon Map of Survey	
Situate in Sections 18 and 19, Township 2 North, Range 39 East of the Willamette Meridian	
UNION COUNTY, OREGON	
SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 1000'	Drawn by: J. S. H. May-June 2013

SURVEY NUMBER 024-2013

