



1 1/2" iron pipe with brass washer marked CX-12 1973 bears South 0°27'20" East, a distance of 22.69 feet. A 5/8" iron pin falls 0.10 feet South of this pipe.

BASIS OF BEARING

The West line of the Southwest quarter of Section 32, Township 4 South, Range 41 East of the Willamette Meridian being North 0°15'31" West, as per Survey Number 22-86, as filed in the office of the Union County Surveyor

SCALE: 1" = 500'

LEGEND

- Found 2 1/2" iron pipe with 3" brass cap, set by BLM surveyor Philip Griffin under special instructions dated July 13, 1979 and June 26, 1990
- ◆ Found 2 1/2" iron pipe with 3" brass cap, set by BLM surveyor Stephen Albright under special instructions dated May 3, 1957
- Found 3" brass cap in concrete, marked as per Union County monumentation record 721-84R, set by Survey Number 016-75
- ⊙ Found 2 1/2" aluminum pipe with aluminum cap, marked as per Union County monumentation records, set by Survey Number 038-1991
- ⊙ Set 5/8" x 30" iron pin with 2 1/2" aluminum cap marked as per Union County Monumentation Records
- [] Record measurement as per Field Notes BLM Special Instruction dated July 13, 1979 and June 26, 1990, executed by Philip Griffin
- () Record measurement as per Survey Number 038-1991

REFERENCE MATERIAL

- Union County Monumentation Records
 - Survey Number 038-1991
 - Survey Number 016-75
 - Survey Number 008-2013
- Field Notes from BLM special instructions dated July 13, 1979 and June 26, 1990, executed by Philip Griffin
- Field notes from BLM special instructions dated May 3, 1957, executed by Stephen Albright

Mircofilm Document Number 20113535

NARRATIVE

This survey was done at the request of Steve McClelland on behalf of Hancock Forest Management, land manager of the lands within. Mr. McClelland wanted the exteriors of the ownership monumented within the Southeast quarter of Section 8. I recover the monuments as shown hereon. I place the new monuments as per BLM Manual of Instructions 2009. I find no unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2015

UNION COUNTY
SURVEYOR
Date Received 12/10/13
Date Filed 12/10/13
By J. S. H.
File No. 054-2013

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey		
Situated in Section 8, Township 5 South, Range 41 East of the Willamette Meridian		
UNION COUNTY, OREGON		
SURVEYED FOR	Hancock Forest Management	
SURVEYED BY	J. S. H.	
Scale: 1" = 500'	Drawn by: J. S. H.	Dec. 2013

SURVEY NUMBER 054-2013