



### BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from  $\Delta$  COLLEGE to  $\Delta$  VALLEY Dated 1946.

**SCALE: 1" = 40'**

### LEGEND

- Found 1" OD pipe, set by Survey Number 48
- ◆ Found 5/8" iron pin, set by Survey Number 99-74
- Found 5/8" iron pin with plastic cap marked BGA SURVEY MARKER, set by Survey Number 31-71
- Found 5/8" iron pin with plastic cap marked BGA SURVEY MARKED, set by Survey Number 10-80
- ⊗ Centerline position established from lead plug references set by Survey Number 028-2005
- ⊙ Set 2" brass cap in concrete marked BAGETT GRIFFITH AND BLACKMAN
- Set brass screw in lead plug with washer marked OPLS 83571 as reference monument
- Centerline
- ( ) Record measurement as per Survey Number 18-89 (1922 monumentation)
- [ ] Record measurement as per Survey Number 99-74
- { } Record measurement as per Survey Number 10-80
- - - Record measurement as per Survey Number 25-82
- / / Record measurement as per Survey Number 18-81
- Ⓜ Manhole

### REFERENCE MATERIAL

- Survey Number 48
- Survey Number 31-71
- Survey Number 25-74
- Survey Number 10-80
- Survey Number 18-81
- Survey Number 25-82
- Survey Number 18-89
- Survey Number 028-2005

### NARRATIVE

This survey was done at the request of Norm Paullus, director of Public Works for the City of La Grande. Mr. Paullus wanted the centerline intersection monuments along G Avenue replaced following a paving project. Prior to paving, I tie the PK Nail at the intersection of G Ave. and 5th Street used in Survey Number 25-82. I find this nail to be harmonious with surveys in the area and set the monument at the tied position. I place the intersection of 6th Street and G Ave. by projecting a line through the found monuments set by Surveys 48 and 31-71 at the Northeast and Southeast corners of Block 29 to establish the West right of way of 6th Street. From the PK Nail position, I drive a line to a point 40 feet from the monument at the Southeast corner of Block 29 to place the G Ave. centerline. I place the intersection of 6th Street and H Ave. by driving a line from the position at 4th Street and H Ave. to a point 40 feet North of the Northeast corner of Block 29, as was done by Survey 18-81. I place the intersection of 5th Street and H Ave by proportion. Monuments as shown hereon are as tied in the field. I find no unusual conditions with this survey.

UNION COUNTY SURVEYOR	
Date Received	2/28/14
Date Filed	2/28/14
By	J. S. H.
File No.	004-2014

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>J. S. H.</i>
OREGON JUNE 2, 2010
JEFFREY S. HSU 83571
Renewal Date: June 30, 2015

<b>BAGETT, GRIFFITH &amp; BLACKMAN</b>	
2006 Adams Avenue, LaGrande, Oregon	
Map of Survey	
Centerline intersection monuments along G Ave. from 5th to 6th Streets, City of La Grande	
UNION COUNTY, OREGON	
SURVEYED FOR	City of La Grande
SURVEYED BY	J. S. H.
Scale: 1" = 40'	Drawn by: J. S. H. Jan.-Feb. 2014