

TOWNSHIP 1 SOUTH 36
TOWNSHIP 2 SOUTH 2

BASIS OF BEARING

The Southeast corner of Section 11 to the Northeast corner of Section 2, Township 2 South, Range 35 East of the Willamette Meridian being North 0°02'02" East, as per Survey Number 027-2003

SCALE: 1"=500'

LEGEND

- Found monument as described, marked as per Union County monumentation records
- ⊙ Set 2 1/2" aluminum pipe with 2 1/2" aluminum cap, marked as per Union County monumentation record, filed separately
- /// Line marked with flagging and paint on adjacent trees
- *— Existing fenceline
- { } Record measurement as per Survey Number 11-82
- () Record measurement as per field notes of GLO Contract No. 451, executed by Rufus Moore

REFERENCE MATERIAL

Union County Monumentation Records
Survey Number 11-82
Survey Number 026-1992
Survey Number 027-2003
Survey Number 030-2008

Field Notes for GLO Contract Number 451, executed by Rufus Moore, dated June 12, 1882

DEED REFERENCES

Microfilm Document Number 20134220
Microfilm Document Number 20045925
Microfilm Document Number 113053

NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager of the land within. Mr. Marolla wanted the corners set and line marked as shown hereon for a future timber sale. I make a diligent search for the controlling monuments of Section 11, but did not find any remaining evidence of original GLO corners at the North, East and West quarter corners or the Northeast section corner. There are double corners at the Northwest corner of Section 1 and the South quarter corner of Section 11. I accept the monuments as described hereon. I position the lost corners by proportionate measurement as per BLM Manual of Instructions 2009. Monuments set by Survey Number 11-82 were proportioned based on a different position of the Northwest corner of Section 1 than the one used in this break and therefore were not accepted. A fenceline along the South line of the Southeast quarter of Section 11 runs North of the property line from between 1 and 10.5 feet. I find no other unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jeffrey S. Hsu
OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2015

UNION COUNTY
SURVEYOR

Date Received 5/29/14

Date Filed 5/29/14

By J. S. H.

File No. 016-2014

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon
Map of Survey

Situate in Section 11, Township 2 South,
Range 35 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR Hancock Forest Management

SURVEYED BY J. S. H.

Scale: 1" = 500' Drawn by: J. S. H. May 2014

