



## BASIS OF BEARING

True Geodetic North at the corner to Sections 19, 20, 29 and 30, Township 1 South, Range 40 East, of the Willamette Meridian, as determined by GPS observation.

SCALE: 1"=500'

## LEGEND

- Found 2 1/2" aluminum pipe with 2 1/2" aluminum cap, marked as per Union County Monumentation Records, set by Survey Number 043-1998
- Found 2 1/2" iron pipe with 2 1/2" brass cap, marked as per Union County Monumentation Records, set by Survey Number 32-80
- ⊙ Set 2 1/2" x 30" aluminum pipe with 2 1/2" aluminum cap, marked as per Union County Monumentation Records, filed separately
- Set 5/8" x 30" iron pin with 2 1/2" aluminum cap, marked as per Union County Monumentation Records, filed separately
- { } Record measurement as per Survey Number 32-80
- [ ] Record measurement as per Survey Number 043-1998
- ( ) Record measurement as per field notes of GLO Contract No. 450, executed by Henry Meldrum, dated June 11, 1882
- Steel fencepost set on line
- x — Fenceline

## REFERENCE MATERIAL

Field notes of GLO contract number 450, executed by Henry Meldrum, dated June 11, 1882

Survey Number 32-80  
 Survey Number 043-1998  
 Partition Plat Number 20120011T  
 Partition Plat Number 20130001T

DEED REFERENCES  
 Microfilm Document Number 125953  
 Microfilm Document Number 20134272

## NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager for the land shown. Mr. Marolla wanted the corners set and the property line marked with steel fenceposts along the portion of the property as shown in preparation for a timber harvest. I recover the monuments as shown hereon. The Southeast corner of Section 15 was placed from the GLO SW bearing tree. No remaining evidence of the original GLO corner at the West or the South quarter corners could be found and I place these by proportionate measurement. I further subdivide the section as per BLM Manual of Instructions 2009. Fencelines are off as shown hereon. I find no other unusual conditions with this survey.

UNION COUNTY  
 SURVEYOR

Date Received 3/19/15

Date Filed 3/19/15

By [Signature]

File No. 018-2015

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

[Signature]

OREGON  
 JUNE 2, 2010  
 JEFFREY S. HSU  
 83571

Renewal Date: June 30, 2015

**BAGETT, GRIFFITH & BLACKMAN**  
 2006 Adams Avenue, LaGrande, Oregon  
 Map of Survey

Situate in Section 15, Township 1 South,  
 Range 40 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR	Hancock Forest Management	
SURVEYED BY	J. S. H.	
Scale: 1"=500'	Drawn by: J. S. H.	Mar. 2015

SURVEY NUMBER 018-2015