



REFERENCE MATERIAL

- Survey Number 48
- Survey Number 31-71
- Survey Number 10-80
- Survey Number 18-81
- Survey Number 17-87
- Survey Number 18-89
- Survey Number 009-1995
- Survey Number 028-2005
- Survey Number 004-2014

BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from Δ COLLEGE to Δ VALLEY Dated 1946.

SCALE: 1" = 50'

LEGEND

- Found 5/8" iron pin, set by Survey Number 009-1995
- ◆ Found 5/8" iron pin with plastic cap marked BGA SURVEY MARKER, set by Survey Number 17-87
- Found 5/8" iron pin with plastic cap marked BGA SURVEY MARKER, set by Survey Number 10-80
- ⊕ Found 2 1/2" brass cap, set by Survey Number 028-2005
- Found lead plug references, set by Survey Number 18-89 (1922 monumentation)
- ▲ Found brass screw in lead plug references, set by Survey Number 028-2005
- ◆ Found brass screw in lead plug references, set by Survey Number 004-2014
- ⊙ Found 2" brass cap in concrete, set by Survey Number 004-2014
- ⊙ Set 2" brass cap in concrete marked BAGETT GRIFFITH AND BLACKMAN
- Set cotton spindle as reference monument
- — — Centerline
- () Record measurement as per Survey Number 18-89 (1922 monumentation)
- [] Record measurement as per Survey Number 028-2005
- { } Record measurement as per Survey Number 17-87
- (()) Record measurement as per Survey Number 004-2014
- / / Record measurement as per Survey Number 18-81
- Ⓜ Manhole

NARRATIVE

This survey was done at the request of Norm Paullus, director of Public Works for the City of La Grande. Mr. Paullus wanted the centerline intersection at H Avenue and Fifth Street monumented following a paving project. The position has been established by Surveys 18-81, 17-87 and 009-1995. All of them use the proportionate distance between the intersection of 4th Street and H Ave and the intersection of 6th Street and H Avenue. In Survey Number 004-2014, I use the same method for the placement of this intersection as well. However, I find that a straight proportion (as per Survey Number 004-2014) does not fit harmoniously with the tied pins set by Survey 17-87 and 009-1995. I therefore place the intersection by careful retracement of these surveys rather than by a mathematical proportion. Lead plugs in H and 4th show evidence of disturbance and I reestablish this position by the intersection positions of 4th and G and I Avenues. I find no other unusual conditions with this survey.

UNION COUNTY SURVEYOR

Date Received 5/27/15

Date Filed 5/27/15

By Neil Gillman

File No. 029-2015

REGISTERED PROFESSIONAL LAND SURVEYOR

J.S.H.

OREGON JUNE 2, 2010

JEFFREY S. HSU 83571

Renewal Date: June 30, 2017.

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon

Map of Survey

Centerline intersection 5th Street and H Avenue, City of La Grande

UNION COUNTY, OREGON

SURVEYED FOR	City of La Grande
SURVEYED BY	J. S. H.
Scale: 1" = 50'	Drawn by: J. S. H. Feb.-May 2015