



BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from Δ COLLEGE to Δ VALLEY Dated 1946.

SCALE: 1" = 60'

LEGEND

- ⊙ Found 2" brass disc in concrete, set by Survey Number 006-2014
- Found 60d spike set by Survey Number 022-2010
- ⦿ Found concrete nail in asphalt set by Survey Number 83-79
- Found 5/8" Iron pin set by Survey Number 13-66
- ◆ Found 5/8" iron pin set by Survey Number 31-69
- ▲ Found 5/8" iron pin set by Survey Number 008-1999
- Found 5/8" iron pin with plastic cap marked BGB SURVEY MARKER, set by Survey Number 022-2010
- ◆ Found 5/8" iron pin with plastic cap marked BGB SURVEY MARKER, set by Survey Number 010-2008, unless otherwise noted
- ⊗ Found lead plugs with brass screw in curb
- ⊙ Set 2" Brass Cap marked BAGETT, GRIFFITH AND BLACKMAN in concrete
- Set lead plug with brass screw and washer marked OPLS 83571
- () Record measurement of Survey Number 18-89
- [] Record measurement of Survey Number 010-2008
- { } Record measurement of Survey Number 022-2010
- (()) Record measurement of Survey Number 008-1999
- [[]] Record measurement of Survey Number 88-78
- [[]] Record measurement of Survey Number 006-2014
- Centerline

REFERENCE MATERIAL

Plat of Romig's Addition to La Grande Survey Number 88-78
 Plat of Wisdom's Addition to La Grande Survey Number 18-89
 Plat of Chaplin's Addition to La Grande Survey Number 8-99
 Survey Number 13-66 Survey Number 010-2008
 Survey Number 31-69 Survey Number 022-2010
 Survey Number 52-74 Survey Number 006-2014

NARRATIVE

This survey was done at the request of Norm Paullus, Public Works director for the City of La Grande. Mr. Paullus wanted the centerline of Penn and Cedar and 'O' and Cedar monumented following a paving project. I retrace surveys 010-2008 and 022-2010 which placed the intersection position of Penn and Cedar at proportionate distance between First St/Penn Ave and Oak St/Penn Ave. 'O' Ave/Cedar St. was placed at proportionate distance between First Street and Oak Street intersections as per Survey Number 022-2010. I find no unusual conditions with this survey.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Jeffrey S. Hsu

OREGON
 JUNE 2, 2010
 JEFFREY S. HSU
 83571

Renewal Date: June 30, 2017

UNION COUNTY
 SURVEYOR

Date Received 2/29/16

Date Filed 2/29/16

By M.G. Miller

File No. 010-2016

BAGETT, GRIFFITH & BLACKMAN
 2006 Adams Avenue, LaGrande, Oregon
 Map of Survey

Intersection of Penn Avenue/Cedar Street and
 'O' Avenue and Cedar Street
 City of La Grande
 UNION COUNTY, OREGON

SURVEYED FOR	City of La Grande
SURVEYED BY	J. S. H.
Scale: 1" = 60'	Drawn by: J. S. H. Feb. 2016