



BASIS OF BEARING

The West line of Section 13, Township 3 North, Range 39 East of the Willamette Meridian being North 0°15'26" East, as per Survey Number 017-2005

SCALE: 1" = 600'

LEGEND

- ⊙ Found 1 1/2" iron pipe with 2" brass cap marked as per Union County monumentation records, set by Survey Number 86-77
- ⊙ Set 2 1/2" aluminum pipe with 3" aluminum cap, marked as per Union County Monumentation records, filed separately
- [] Record measurement as per Survey Number 001-1996
- { } Record measurement as per Survey Number 86-77
- () Record measurement as per field notes of GLO contract no. 498, dated March 10, 1884

REFERENCE MATERIAL

- Union County Monumentation Records
Survey Number 86-77
Survey Number 001-1996
- Field Notes of GLO contract no. 437, dated June 3, 1882, completed by Rufus S. Moore
- DEED REFERENCES
Microfilm Document Number 20134270
Microfilm Document Number 20134275

NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager of the land within. Mr. Marolla wanted the corners set, as shown hereon, prior to a timber sale. I recover the monuments as shown. I make a diligent search for the Northeast corner and the East quarter corner of Section 12, but find no remaining evidence of either. This is the situation encountered in Surveys 86-77 and 001-1996. I place these corners at proportionate position. I find no unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2019

UNION COUNTY
SURVEYOR

Date Received 11/8/17

Date Filed 11/8/17

By *[Signature]*

File No. 042-2017

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon

Map of Survey

Situate in Sections 1 and 12, Township 3 North, Range 39 East and Sections 6 and 7, Township 3 North, Range 40 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 600'	Drawn by: J. S. H. Nov. 2017