



### BASIS OF BEARING

Geodetic North at the corner common to Sections 7, 8, 17 and 18, Township 6 South, Range 38 East of the Willamette Meridian, as determined by GPS observation

SCALE: 1" = 500'

### LEGEND

- ⊙ Found 2 1/2" iron pipe with 2 1/2" brass cap, marked as per monumentation records, set by Union County Survey Number 95-79
- ⊙ Found 2 1/2" iron pipe with 2 1/2" brass cap, marked as per monumentation records, set by Union County Survey Number 23-81 (Baker County Survey Number 06-38-0001)
- Found 1" iron pipe with 2 1/2" brass cap, set by James Hanley in Baker County Survey Number 06-38-0014
- Set 5/8" x 30" iron pin with 2 1/2" aluminum cap, marked as per Baker County Monumentation records, filed separately
- Steel fencepost set on line
- ( ) Record measurement as per Union County Survey Number 23-81/Baker County Survey Number 06-38-0001
- x- Fenceline
- - - - - Creek

### REFERENCE MATERIAL

**Union County Monumentation Records**  
 Union County Survey Number 95-79  
 Union County Survey Number 23-81  
 Union County Survey Number 44-81  
 Union County Survey Number 050-1991  
 Baker County Survey Number 06-38-0001  
 Baker County Survey Number 06-38-0014

#### UNION COUNTY DEED REFERENCES

Microfilm Document Number 136011  
 Microfilm Document Number 20023072  
 Microfilm Document Number 20132730  
 Microfilm Document Number 20134269  
 Microfilm Document Number 20134274  
 Microfilm Document Number 20132731  
 Microfilm Document Number 20140117

#### BAKER COUNTY DEED REFERENCES

Microfilm Document Number B12 39 0261  
 Microfilm Document Number B13 49 0261  
 Microfilm Document Number B16 46 0303

### NARRATIVE

This survey was done at the request of Patrick Marolla on behalf of Hancock Forest Management, land manager of the lands within. Mr. Marolla wanted lines within Section 18 monumented and posted prior to a timber harvest. I recover the monuments set by Survey Number 95-79 and 23-81 (filed in Baker County as 06-38-0001). I find the monuments harmonious with record measurements and accept them in place. Subdivision of the section is as per BLM Manual of Instructions 2009. Fencelines are off as shown. I find no unusual conditions with this survey.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

OREGON  
 JUNE 2, 2010  
 JEFFREY S. HSU  
 83571

Renewal Date: June 30, 2019

UNION COUNTY  
 SURVEYOR

Date Received 11/15/17

Date Filed 11/15/17

By J. S. H.

File No. 046-2017

**BAGETT, GRIFFITH & BLACKMAN**  
 2006 Adams Avenue, LaGrande, Oregon  
 Map of Survey

Situate is Section 18, Township 6 South,  
 Range 38 East of the Willamette Meridian

UNION/BAKER COUNTIES

SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 500'	Drawn by: J. S. H. Nov. 2017

SURVEY NUMBER 046-2017